

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 12 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Petroleum Incorporated

Complete Address: Route 2, Great Bend, KANSAS

Lease Name ELLENWOOD, W. W. D. Well No. #1

Location Ne-SE~~3~~-Nw Sec. 34 Twp. 34 Rge. 13 (E) (W) w

County Barber Total Depth 3830

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Southwest Casing Pulling Co.

Address: B or 364 Great Bend Kansas License No. 399

Operation Completed: Hour 1:30 PM Day 4 Month 10 Year 1964

The Above well was plugged as follows:

289 feet of 8 5/8" Surface Pipe cemented with 175 sacks; 396 feet of 4 1/2" Long

String cemented with 60 sacks cement. Perforations have been squeezed. ~~Max 1000~~

~~feet~~ Sand to 3680 cemented with 3 sacks. Mud to 250 feet, 10 foot Rock Bridge, 20 sacks

cement. Hole filled to 40 ft., 10 foot Rock Bridge; 10 sacks of cement to base of

cellar. 3265 ft of <sup>4 1/2"</sup> Long String Recovered

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Harman Justus  
Well Plugging Supervisor

DATE 10/12/64

INV. NO. 9961-U