

40
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC 3 1962
12-3-62
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum Inc.

Complete Address: R.R.#2, Great Bend, Kansas.

Lease Name Houston "C" #2 Well No. #2

Location C-E/2 SE NW Sec. 34 Twp. 34 Rge. 13 (E) (W) X

County Barber Total Depth 3648'

Abandoned Oil Well Abandoned Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Caseing Pulling Co.

Address: Box 364 Great Bend, Kansas. License No. 399

Operation Completed: Hour 4:PM Day 29 Month Nov. Year 1962

The Above well was plugged as follows:

3647' of 4 1/2" long string cemented with 75 sacks cement & 3 sacks gel.
Perforated between 3643' & 3646'. Sanded to 3630' & 3 sacks cement. 310'
of surface pipe (8 5/8") circulated with 175 sacks cement. Hole filled to
200' with mud. 10' rock bridge. 20 sacks cement. Hole filled to 40' with
mud. 10' rock bridge. 10 sacks cement to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/4/62

INV. NO. 6137-W

Signed: Herman J. Justice
Well Plugging Supervisor