

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAY 23 1966

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name L. O. Tenk

Complete Address: Box 294, Ottawa, Kansas

Lease Name Emma House Well No. # 2

Location C SW NW Sec. 15 Twp. 30 Rge. 12 (E) (W) W

County Barber Total Depth 4591'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Strata Drilling, Inc.

Address: 2421 Tenth St., Great Bend, Kansas License No.

Operation Completed: Hour 8:00PM Day 15th Month May Year 1966

The Above well was plugged as follows:

405' of 8 5/8" surface pipe, cement circulated with 300 sacks. Hole
was filled with drilling mud to 300', 1st cementing plug bridged with
1/2 sack of hulls on fluid at 300', and cemented with 25 sacks. Hole was
filled with drilling mud to 40', 2nd cementing plug, bridged with 1/2
sack of hulls on fluid at 40', and cemented with 10 sacks to the base
of the cellar. Rat and mouse holes bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/23/66
INV. NO. 3260-W