

Form CP-3
Rev. 6-26-62

M
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 17 1967
1-17-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Intent to Drill, filed
January 3, 1967

Operator's Full Name California Time Petroleum, Inc.

Complete Address: P. O. Box 8124, Wichita, Kansas

Lease Name House Well No. # 1

Location C SW SW Sec. 15 Twp. 30 Rge. 12 (E) (W) W

County Barber Total Depth 4476'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Strata Drilling, Inc.

Address: Box 355, Great Bend, Kansas License No.

Operation Completed: Hour 2:30AM Day 16th Month Jan. Year 1967

The Above well was plugged as follows:

310' of 8 5/8" surface pipe, cement circulated with 225 sacks. Hole
was filled with drilling mud to 300', 1st cementing plug, bridged with
2 sacks of dry cement and 1/2 sack of hulls on fluid at 300', and cemented
with 23 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at
40', and cemented with 9 sacks to the base of the cellar. Rat hole bridged
and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 1/19/67
INV. NO. 4631-u

Signed: Archie Elving
Well Plugging Supervisor