

RECEIVED  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION  
 JAN 30 1989

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE NAME K D Lemon ET AL

WELL NUMBER 1

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 16 TWP. 30S RGE. 13 XXXXX (W)

COUNTY Barber

Date Well Completed 1-22-89

Plugging Commenced 1-22-89

Plugging Completed 1-22-89

EASE OPERATOR RAMCO Energy Corporation

ADDRESS 127 Lee Street, P. O. Box 99, Belpre, OH 45714

PHONE# (614) 423-9591 OPERATORS LICENSE NO. 3536

Character of Well D&A

Oil, Gas, D&A, SWD, Input, Water Supply Well

The plugging proposal was approved on 1-22-89 (date)

by State Plugger, Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4602'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				13 3/8"	139'	None
				8 5/8"	1085'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. Circulate heavy mud in hole. 1st plug from 1100' to 900' w/50 sx. 2nd plug from 500' to 340' w/40 sx. 3rd plug from 40' solid bridge to surface w/10 sx. Rathole-15 sx. Mousehole-10 sx. All cement 60/40 posmix, 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: RAMCO Energy Corporation


STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801  
 Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 24th day of January, 1989



Janet A. Stuck  
 Notary Public

Commission Expires: 12-29-90