

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

-00-01

API NUMBER 007-22,218-A

LEASE NAME Lemon

WELL NUMBER 1-A

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 16 TWP. 30 RGE. 13 (S) or (W)

COUNTY Barber

Date Well Completed 9/25/90

Plugging Commenced 7/19/93

Plugging Completed 7/21/93

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Woolsey Petroleum Corp.

ADDRESS 107 N Market #600 Wichita, KS 67202

PHONE# (316) 267-4379 OPERATORS LICENSE NO. 5506

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/26/93 (date)

by D.P. Williams (Duane Rankin) (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached?

Producing Formation Viola Depth to Top 4540' Bottom 4594' T.D. 4650'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Viola 4540-4594</u>	<u>Oil-water</u>	<u>Surface</u>	<u>139'</u>	<u>13 7/8"</u>	<u>139'</u>	<u>-0-</u>
<u>Arbuckle 4484-4700</u>	<u>Oil-water</u>	<u>Surface</u>	<u>1085'</u>	<u>8 5/8"</u>	<u>1085'</u>	<u>-0-</u>
		<u>Surface</u>	<u>4754'</u>	<u>5 1/2"</u>	<u>4754'</u>	<u>3794'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Set CIBP @ 4488' - 25sax Common Cement on top of CIBP w/ baler.
From surface pump 300# balls, 1000# gel, 50 sax 60/40 + 6% gel, 1000#
gel, 100# balls, 8 3/4" wiper plug, 5 100 sax 60/40 + 6% gel. Final pressure 600 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address Attica, KS 67009

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Woolsey Petroleum Corp.

STATE OF _____ COUNTY OF _____, ss.

Carl W. Durr (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, STATE CORPORATION COMMISSION me God.

(Signature) Carl W. Durr

(Address) R#1 Box 16A-3 Milton, KS 67106

AUG - 2 1993

SUBSCRIBED AND SWORN TO before me this 30th day of July, 19 93

Summer Co. Kansas Maurice Colter

My Commission Expires: Apr: 1 13 96 Not

