


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 15 Twp. 30S Rge. 13W (E) (W)  
Location as "NE/CNWxSWx" or footage from lines. SE SW SW  
Lease Owner J. O. Forbes  
Lease Name Grigsby Well No. # 1  
Office Address P. O. Box 221 Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed yes 19\_\_\_\_  
Application for plugging approved yes 19\_\_\_\_  
Plugging commenced 2-19-61 19\_\_\_\_  
Plugging completed 2-23-61 19\_\_\_\_  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4323' PB Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		3,898'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugging commenced 2-19-61. Plugging completed 2-23-61.  
Measured in to total depth: Plug at 4323'.  
Plugged off bottom: Sanded back to 4175' and dumped  
5 sacks of cement.  
Worked and shot 5 1/2" casing free at 3,898'.  
Built rack and slide.  
Pulled and layed down casing.  
Plugged well: Mudded up to 250' and set 10' rock bridge.  
dumped 20 sacks of cement.  
Mudded up to 40' and set 10' rockbridge.  
Capped the well with 10 sacks of cement.

**RECEIVED**  
STATE CORPORATION COMMISSION  
MAY 25 1961  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Co.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
J. O. Forbes  
Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 30th, day of April, 1961

My commission expires December 8th, 1963.

Kayann Jenkins  
Kayann Jenkins  
Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
 508 East Murdock, Wichita, Kansas


COPY

Company BURWICK & BROOKS HALL  
 Farm Grigsby No. 1

SEC. 15 T. 30 R. 13W  
 SE SE SW

Total Depth. 3815  
 Comm. 12-10-54 Comp. 12-18-54  
 Shot or Treated.  
 Contractor. Burwick  
 Issued. 4-2-55

County Barton KANSAS



Elevation. \_\_\_\_\_

Production. dry

CASING:

No Casing Reported

Figures indicate Bottom of Formations.

surface soil	60
shale & redbed	212
shale	340
sand & shale	430
shale & shells	1080
lime	1105
redbed & shale	1550
shale & shells	1835
lime & shale	2200
shale	2285
lime & shale	3085
lime	3160
lime & shale	3330
sand	3355
lime	3470
lime & shale	3815
Total depth	

Tops:	
Hebner	3724
Toronto	3740
Douglas	3794

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 OCT 2 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas