

15-007-21150-00-00

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Barber SEC. 27 TWP. 30S RGE. 13 XXW  
 Location as in quarters or footage from lines:  
660' FSL and 660' FEL


Lease Owner Texas Oil and Gas Corporation  
 Lease Name Hartley "A" Well No. 1  
 Office Address 200 W. Douglas, Suite 300, Wichita, KS 67202  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed April 12, 1981  
 Application for plugging filed Verbal Application  
 Plugging commenced April 11, 1981  
 Plugging completed April 12, 1981  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4,016'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8	249'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,016 ft. (rotary total depth) to 934 ft. Set plug at 934 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 934 ft. to 252 ft. Set plug at 252 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 252 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement. 10 sacks cement in rat hole, 5 sacks cement in mouse hole.

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 28 1981  
 CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor H-30, INC.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Dean Britting, Agent ~~XXXXXX~~ (Employee of owner) ~~XXXXXXXXXXXXXXXXXXXX~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting  
251 N. Water, Suite 10, Wichita, KS  
 (Address) \_\_\_\_\_ 67202



SUBSCRIBED AND SWORN TO before me this 27th day of April, 19 81

Elsie Willison  
 Notary Public.

My Commission expires: July 25, 1992

KANSAS DRILLERS LOG

COMPANY Texas Oil and Gas Corporation

SEC. 27 T. 30S R. 13W

FARM Hartley "A" NO. 1

LOC. 660' FSL and 660' FEL

ROTARY TOTAL DEPTH 4,016'

COUNTY Barber

COMM. April 4, 1981

COMP. April 12, 1981

CONTRACTOR H-30, INC.

ISSUED April 24, 1981

CASING

10 3/4"	
8 5/8"	249' cemented w/400 sacks cement
5 1/2"	
4 1/2"	

ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed	124'
Red Bed and Shale	2,064'
Lime and Shale	2,510'
Shale and Lime	3,130'
Lime and Shale	3,840'
Shale and Lime	3,858'
Sand	3,964'
Lime and Shale	4,016'
RTD	4,016

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Dean Britting*  
 \_\_\_\_\_  
 Dean Britting

State of Kansas )  
 ) ss:  
 County of Sedgwick )

Subscribed and Sworn to before me a Notary Public in and for said county and state this 24th. day of April, 1981.

*Elsie Willison*  
 \_\_\_\_\_  
 Elsie Willison -Notary Public

My Commission Expires:

July 25, 1981

RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 28 1981  
 CONSERVATION DIVISION  
 Wichita, Kansas

