

LEASE NAME Rauhut

WELL NUMBER 1"A"

660 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 18 TWP. 30 RGE. 13 (E) or (W)

COUNTY Barber

Date Well Completed 09-06-90

Plugging Commenced 09-06-90

Plugging Completed 09-06-90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Raymond Oil Company, Inc.

ADDRESS P.O. Box 48788 Wichita, KS 67201

PHONE# (316) 267-4214 OPERATORS LICENSE NO. 5046

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 09-04-90 (date)

by Mr. Goodrow (KCC District Agent's Name).

to be filed
is ACO-1 filed? by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4670'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Bottom Plug: @760' w/70 sack cement thru drill pipe
Next Plug: @300' w/70 " " " " " 15 sacks in Bar Hole
Top Plug: @40' w/15 " " " " " 10 sacks in Mouse hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Lobo Drilling Company License No. 5864

Address P.O. Box 877 Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Raymond Oil Company, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Ervin Neighbors (Employee of Operator) or ~~(Operator)~~ of


above-described well, being first-duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ervin Neighbors

(Address) P.O. Box 877 Great Bend, KS 67530

SEP 12 1990
9-12-90

SUBSCRIBED AND SWORN TO before me this 10 day of Sept., 1990



Dorothy M. Hague
Notary Public

DRILLER'S WELL LOG

DATE COMMENCED: August 30, 1990
DATE COMPLETED: September 6, 1990

Raymond Oil Company, Inc.
RAUHUT #1-A
C SE SW
Sec. 18, T30S, R13W
Barber County, Ks.

ELEVATION: 1849 K.B.

0 - 70' Surface Soil, Sand
70 - 273' Red Bed, Shale
273 - 4480' Shale & Lime
4480 - 4587' Chert & Lime
4587 - 4670' Shale & Sand
4670' RTD

Surface Pipe: Set used
10-3/4", 28# pipe @269'
w/225 sacks 60/40pozmix
2% gel 3% cc.

A F F I D A V I T


STATE OF KANSAS
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 10 day of September 1990.

Dorothy M Hague
Notary Public



SEP 12 1990