


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 19 Twp. 30S Rge. 13 ~~XXX~~ (W)

Location as "NE/CNW/SW" or footage from lines NW NE
Lease Owner Rains & Williamson Oil Co.
Lease Name Lenkner Well No. 1
Office Address 1425 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-15-65 19 65
Application for plugging filed 9-21 19 65
Application for plugging approved 9-15-65 19 65
Plugging commenced 9-15 19 65
Plugging completed 9-15 19 65
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes, verbally

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4641 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	350	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 300'
Set first plug at 300' with 300 sacks cement, 1/4 sack hulls
Filled with heavy mud to 50'
Set second plug at 50' with 15 sacks cement, 1/4 sack hulls, 5 sacks cement in rathole

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bowers Drilling Company, Inc.
Address 1434 Wichita Plaza, Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Emil E. Bowers

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers
1434 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of September, 19 65

My commission expires May 1, 1966
Donna F. Miller Notary Public.



WELL LOG

COMPANY: Rains & Williamson Oil Co.
 CONTRACTOR: Bowers Drilling Company, Inc.
 FARM: Lenkner #1
 LOCATION: NW NE Section 19-30S-13W
 Barber County, Kansas
 COMMENCED: 9-1-65
 COMPLETED: 9-15-65
 ELEVATION: 1832 Kelly Bushing

0 - 362 Redbed
 362 - 1000 Redbed, shale & shells
 1000 - 2000 Shale and shells
 2000 - 2091 Shale and lime
 2091 - 2823 Lime
 2823 - 3185 Lime and shale
 3185 - 3484 Lime
 3484 - 3730 Lime and shale
 3730 - 3865 Lime, shale and sand
 3865 - 3937 Lime and shale
 3937 - 4034 Lime
 4034 - 4072 Lime and Sh. breaks
 4072 - 4145 Lime
 4145 - 4174 Lime-chalk
 4174 - 4547 Lime
 4547 - 4598 Lime-chert
 4598 - 4624 Lime
 4624 - 4639 Lime-sand
 4639 - 4641 Sand
 4641 T. D.

RECEIVED
 STATE CORPORATION COMMISSION

SEP 22 1965

CONSERVATION DIVISION
 Wichita, Kansas

LOG TOPS:

Heebner	3736	Kinderhook	4445
Douglas	3776	Viola	4483
Lansing	3920	Simpson Shale	4605
Mississippian	4422	Simpson Sand	4642

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the copy of the log of the Lenkner #1 located NW NE Section 19-30S-13W, Barber County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

Emil E. Bowers
 Emil E. Bowers

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 21st day of September, 1965.

Donna F. Miller
 Donna F. Miller, Notary Public

My commission expires May 1, 1966.

