


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 17 Twp. 30S Rge. 13W (E) (W) X
Location as "NE/CNW&SW" or footage from lines NO. WEST SW SE
Lease Owner Glen N. Rupe
Lease Name Lemon Well No. 1
Office Address 925 Olive Garvey Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D&A
Date well completed October 11 19 72
Application for plugging filed October 11 19 72
Application for plugging approved October 11 19 72
Plugging commenced October 11 19 72
Plugging completed October 11 19 72
Reason for abandonment of well or producing formation D&A

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4650 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	1014'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/mud up to 800', set 1/2
sx hulls, plug cemented w/40 sx. Filled
hole up to 60' 1/2 sx hulls, plug 15 sx
cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 3 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Virginia K. Albert (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) Virginia K. Albert
1720 Wichita Plaza, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 30th day of October, 19 72

My commission expires July 25, 1976.
Barbara L. Derleed
Notary Public.



DRILLERS LOG

No. 1 Lemon

CASING RECORD:	COMPANY:	Glen N. Rupe	DESCRIPTION:
8-5/8" @ 1014'	CONTRACTOR:	Red Tiger Drilling Co.	20' West of SW SE
w/220 sx cement	COMMENCED:	September 26, 1972	17-30S-13W
TOTAL DEPTH: 4650'	COMPLETED:	October 11, 1972	Barber County, Kansas
			ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	30	
Redbed	30	184	
Shale & Sand	184	425	
Redbed	425	540	
Sand & Shale	540	840	
Shale	840	1612	
Blane Anhydrite	1612	1630	
Shale	1630	1785	
Shale & Lime	1785	2760	
Shale Chalk Lime	2760	3030	
Shale & Lime	3030	3200	
Lime Shale	3200	3440	
Lime	3440	4400	
Chert	4400	4427	
Lime w/Chert	4427	4455	
Lime	4455	4505	
Chert	4505	4540	
Lime	4540	4570	
Sand-Shale-Chert-Lime	4570	4605	
Lime	4605	4640	
Arbuckle Dolomite	4640	4650	

RECEIVED
STATE CORPORATION COMMISSION
NOV 3 1972
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Virginia K. Albert
Virginia K. Albert

Subscribed and sworn to before me this 30th day of October, 1972.

Barbara L. Dorland
Notary Public

My Commission Expires:
July 25, 1976

