


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Barber County. Sec. 28 Twp. 33 Rge. 13 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines SW NW NW
Lease Owner Honaker-Davis Drlg. Co.
Lease Name McKaig Well No. 1
Office Address 2008 Lakin, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Abandoned Well
Date well completed 1-26 19 57
Application for plugging filed 1-26 19 57
Application for plugging approved 1-26 19 57
Plugging commenced 1-26 19 57
Plugging completed 1-26 19 57
Reason for abandonment of well or producing formation In completing well
the casing collapsed
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Merrill Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4685 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TD	SIZE	PUT IN	PULLED OUT
				8-5/8	252	None
				5-1/2	4684	3847

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud to 250'. Dumped in 1/3 sack hulls. Set plug. Dumped in 20 sacks cement through drill pipe.

Filled hole with heavy rotary mud to 35'. Dumped in 1/3 sack hulls. Set Plug. Dumped in 10 sacks cement which filled hole to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF BARTON, ss.
H. S. Forbes, Partner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H. S. Forbes*

(Address) _____

SUBSCRIBED AND SWORN to before me this 29th day of January, 1957

My commission expires 6-25-59

South O. Fisher
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 28 T 33 R 13W
BOOK PAGE 136 LINE 40

JAN 30 1957
1-30-57
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

15-007-00412-0000

McKalg No. 1
 Loc: SW NW NW
 Sec: 28-13-13
 Barber County, Kansas
 Company: Humber-Davis Drig. Co., et al.
 Contractor: Humber-Davis Drig. Co.

Came: 12-10-56
 Comp: 12-24-56
 Rotary Total Depth: 4685'
 Casing: 8-5/8" at 252'
 5-1/2" at 4685'

0	25	Sand	
25	45	Red Bed	
45	140	Sand	8-5/8" casing cemented at 252'
140	1100	Red Bed & Shells	with 200 sacks cement and 25
1100	1289	Red Bed & Shale	calcium chloride.
1280	1340	Shale	
1340	1370	Anhydrite	
1370	1620	Shale, Shells & Salt	
1620	1640	Second Anhydrite	
1640	1700	Shale	
1700	2045	Shale & Lime	
2045	2600	Lime & Shale	
2600	2810	Shale w/Lime Streaks	
2810	2980	Shale & Shells w/Lime Streaks	
2980	3100	Shale	
3100	3285	Shale & Lime	
3285	3405	Lime & Shale	
3405	3485	Shale & Lime	
3485	3555	Lime	
3555	3825	Lime & Shale	
3825	3930	Shale & Lime	
3930	4685	Lime	5-1/2" casing cemented at 4685'
4685		Total Rotary Depth	with 75 sacks cement.

I certify that this is the true and correct copy of the above log to the best of my knowledge.

H. S. Forbes

 H. S. Forbes

Subscribed and sworn to before me this 27th day of December, 1956.

Kenneth G. Fischer

 Kenneth G. Fischer, Notary Public

My commission expires: 6-25-59

PLUGGING
 FILE SEC 28 T. 33 R. 13W
 BOOK PAGE 136 LINE 40

RECEIVED
 STATE CORP. COMMISSION
 JAN 2 1957
 1-30-57
 CONSERVATION DIVISION
 Wichita, Kansas