

Give All Information Completely
Make Required Affidavit - Mail
Or Deliver Report To:

Conversation Division
State Corporation Commission
200 Colorado Derby Building
Wichita, Kansas 67202

Barber County, Sec. 11 Twp. ³³~~258~~ Rge. 14 EXW
Location As "NE/CNW 1/4 SW1/4" Or Footage From Lines
C SE/4 NW/4

Lease Owner Geoson Oil Co., Inc.

Lease Name Angell Well No. #1

Office Address 212 N. Market, Suite 508, Wichita,
KS 67202

Character Of Well (Completed As Oil, Gas Or Dry Hole)

Dry Hole

Date Well Completed March 7 19 81

Application For Plugging Filed March 7, 19 81

Application For Plugging Approved March 7, 19 81

Plugging Commenced March 7, 19 81

Plugging Completed March 7, 19 81

Reason For Abandonment Of Well Or Producing Formation

Dry Hole

If A Producing Well Is Abandoned, Date Of Last Production

19

Was Permission Obtained From The Conservation Division Or
Its Agents Before Plugging Was Commenced? Yes

Name Of Conservation Agent Who Supervised Plugging Of This Well Mr. William H. Owen

Producing Formation _____ Depth To Top _____ Bottom _____ Total Depth Of Well 4815'

Show Depth And Thickness Of All Water, Oil And Gas Formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

RECEIVED
MAR 20 1981
3-20-81
CONSERVATION DIVISION
STATE OF KANSAS

Describe In Detail The Manner In Which The Well Was Plugged, Indicating Where The Mud Fluid Was
Placed And The Method Or Methods Used In Introducing It Into The Hole. If Cement Or Other Plugs
Were Used, State The Character Of Same And Depth Placed, From _____ Feet To _____ Feet
For Each Plug Set.

Plugged at 260' with 40 sacks of common cement, 3% Ca Cl, 2% gel (Howco)

Plugged at 40' with 10 sacks of common cement, 3% Ca Cl, 2% gel (Howco)

Plugged rat hole with 10 sacks of common cement, 3% CaCl, 2% gel (Howco)

Please Note: (If Additional Description If Necessary, Use Bank Of This Sheet)

Name Of Plugging Contractor _____

State Of Kansas County Of Sedgwick ss:

I, J. V. Crawford - Secretary/Treasurer - Ramco Drilling Corporation of the above described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and
matters herein contained and the log of the above described well as filed and that same are true
and correct. So help me God.


THE RAMCO DRILLING CORPORATION

Signature: J. V. Crawford
J. V. Crawford - Secretary/Treasurer
P. O. Box 367, Andover, KS 67002
(Address)

Subscribed And Sworn To Before Me This 18th Day Of March, 1981

Kathy G. Lewis
Kathy G. Lewis Notary Public

My Commission Expires: August 29, 1981



W E L L L O G

WELL NAME: #1 Angell OPERATOR: Geoson Oil Co., Inc.
 SPUD DATE: February 26, 1981 CONTRACTOR: Ramco Drilling Company
 COMPLETION DATE: March 7, 1981 CASING: 8-5/8" @ 279' w/ 250 sacks
 50/50 Pozmix, 3% CaCl, 2% gel.

LOCATION:
 C SE NW Section 11-³³~~25~~S-14W
 Barber County, Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand	0	279
Sand - Shale	279	2495
Shale	2495	2700
Sand and Shale	2700	2906
Shale - Sand	2906	3093
Shale	3093	3291
Shale - Sand	3291	3615
Shale w/Lime	3615	4065
Shale w/ Sand and Lime	4065	4225
Shale - Lime	4225	4675
Lime - Shale	4675	4760
Shale - Lime	4760	4815
Rotary Total Depth		4815

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 29 1981
 5-29-81
 CONSERVATION DIVISION
 Wichita, Kansas


STATE OF KANSAS
 COUNTY OF SEDGWICK

I certify that the above information is true and correct to the best of my knowledge.

THE RAMCO DRILLING CORPORATION

By: J. V. Crawford
 J. V. Crawford, Secy-Treas.
 18th day of March, 1981.

Kathy G. Lewis
 Kathy G. Lewis Notary Public



Appointment Expires: August 29, 1981