


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 11 Twp. 33S Rge. 020X14 (W)

Location as "NE/CNW\*SW\*" or footage from lines C SE/4 SE/4 SE/4  
Lease Owner Sohio Petroleum Company  
Lease Name Angell Well No. 1  
Office Address Box 673, Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 1-12 19 54  
Application for plugging filed 1-12 19 54  
Application for plugging approved 1-13 19 54  
Plugging commenced 1-12 19 54  
Plugging completed 1-12 19 54  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation Depth to top Bottom Total Depth of Well 5327 Feet  
Show depth and thickness of all water, oil and gas formations. R.T.D.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	378'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded hole from TD to 300'.  
Bridged hole 300' with 1 sack cottonseed hulls and wood plug.  
Cemented with 20 sax common cement through open end drill pipe.  
Mudded to 40'.  
Bridged hole with 1/2 sack hulls and wood plug.  
Tied with steel line at surface & cemented to bottom of cellar with 10 sax.  
Well plugged as of 8:30 A.M. 1-12-54

RECEIVED  
JAN 16 1954  
1-16-54  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Musgrove Petroleum Company  
Address Wichita, Kansas

STATE OF KANSAS COUNTY OF RUSSELL ss.  
D. W. SMITH (employee of owner)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. W. Smith

(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of January 1954

My Commission Expires July 2, 1957  
My commission expires  
Russell M. Miller Notary Public.

PLUGGING  
FILE SEC 11 T 33 R 14 W  
BOOK PAGE 7 LINE 23

15-007-00560-0000

CONTRACTOR'S WELL LOG

COMPANY:	Sohio Petroleum Company
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	#1 Angell
LOCATION:	SE SE SE, Sec. 11-33S-14W, Barber County, Kansas.
COMMENCED:	December 18, 1953
COMPLETED:	January 11, 1954

0	110	Clay & red bed
110	150	Sand, shells & shale
150	898	Red bed & shells
898	1990	Shale & shells
1990	2093	Shale & lime & shells
2093	2230	Lime
2230	2430	Lime & shale
2430	2506	Lime
2506	3957	Lime & shale
3957	3965	Elgin Sand
3965	4035	Lime, shale sand
4035	4205	Lime & shale
4205	4268	Lime
4268	4412	Lime & shale
4412	4460	Lime
4460	4540	Lime & shale
4540	4585	Lime
4585	4751	Lime & shale
4751	4801	Mississippi
4801	4846	Lime & shale
4846	4854	Lime
4854	4898	Lime & shale
4898	4971	Lime
4971	5023	Lime & shale
5023	5064	Lime
5064	5169	Lime & chert
5169	5177	Simpson
5177	5273	Shale & simpson
5273	5321	Arbuckle
	5321	Rotary Total Depth

Set 8-5/8" surface pipe at 382' with 250 sacks of cement & 4 C. C.  
Dry and Abandoned.

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the Angell #1, SE SE SE, Section 11-33South - 14 West, Barber County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

*Gordon L. Koelling*  
Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 14th day of January, 1954.

*Notary Public*  
Notary Public

My commission expires September 24, 1956.

PLUGGING  
FILE 11-33-14W  
BOOK 7 LINE 23

1-16-54