

API NUMBER 15-007-21,905-0000

LEASE NAME Elmer Angel

WELL NUMBER #1

660' Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 10 TWP. 33 RGE. 14 (W) or (E)

COUNTY Barber

Date Well Completed 9-8-84

Plugging Commenced 9-8-84

Plugging Completed 9-8-84

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Bowen Oil & Exploration, Inc.

ADDRESS 720 North Main Suite 320

PHONE#(316 665-6563) OPERATORS LICENSE NO. 7077

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, KS

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation XXXXX Depth to Top XXXXXX Bottom XXXX T.D. XXXX

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				16"	40'	0
				8 5/8"	1007'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well with 85 sxs 60/40 poz, 2% gel, 3% cc as follows:
1050' 50sxs; 40' 10 sxs; Rathole-15sxs, Mousehole-10sxs
by Sun Cementing
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Wheatstate Drilling Company License No. 5149

Address Box 329, Pratt, Kansas 67124

STATE OF Kansas COUNTY OF Reno, ss.

Ralph G. Bowen (~~Employee of Operator~~ or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ralph G. Bowen

(Address) 720 N Main, Ste 320, Hutchinson, KS



DESCRIBED AND SWORN TO before me this 4th day of December, 19 84

Karen L. Washburn
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION

DEC 05 09AM
 12-5-84
 CONSERVATION DIVISION
 Wichita, Kansas

Commission Expires: September 26, 1988



Oilfield Services, Inc.

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLER'S WELL LOG

Elmer Angel, Jr. #1
 C SW SE Sec. 10-33S-14W
 Barber County, Kansas
 Commenced: 8-28-84
 Completed: 9-8-84
 API #15-007-21,905-0000
 Operator: Bowen Oil & Exploration

Depth		Formation	Remarks
From	To		
0	40	Conductor Pipe	Set 40', 16" conductor pipe with 3½ yards (6 sx). Job by Jr.'s Rathole.
40	490	Red Bed	
490	1055	Red Bed, Shale	
1055	1555	Shale	
1555	5050	Lime, Shale T.D.	Ran 24 joints (1007') new, 23#, 8 5/8" surface casing. Set at 1022' with 125 sxs Common, 2% gel, 3% cc. Plug down at 1 p.m. Cement did not circulate. 1" top 80' with 50 sxs Common, 2% gel, 3% cc to bottom of cellar. Job by Sun Cementing, ticket #19758. Complete at 1:20 p.m. on August 29, 1984. RTD 5050'.

Y { Plugged well with 85 sxs 60/40 poz, 2% gel, 3% cc as follows: 1050'-50 sxs; 40'-10 sxs; Rathole-15 sxs; Mousehole-10 sxs. Job by Sun Cementing, ticket #19145. Complete at 1:30 p.m. on September 9, 1984. State Plugger was out of the Dodge City, Kansas Office.

STATE OF KANSAS)
) ss
 COUNTY OF PRATT)

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

E. R. Belding
 E. R. BELDING, VICE-PRESIDENT

Mary L. Tjaden
 NOTARY PUBLIC

RECEIVED
 STATE CORPORATION COMMISSIONARY PUBLIC - State of Kansas
 MARY L. TJADEN
 My Appt Exp. 3/22/88
 DEC 05 10 22 AM '84
 CONSERVATION DIVISION
 Wildlife, Kansas
 Commission Expires:

3/22/88