

15-007-00613-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
217 North Market, Insurance Bldg.
Wichita, Kansas

BARBER County, Sec. 9 Twp. 33S Rge. 14W (#) (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner PETROLEUM, INC.

Lease Name MCGRATH "B" Well No. 1

Office Address ROUTE 2, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) GAS WELL

Date well completed MAY 6 1958

Application for plugging filed FEBRUARY 15 19 60

Application for plugging approved FEBRUARY 15 19 60

Plugging commenced FEBRUARY 15 19 60

Plugging completed FEBRUARY 17 19 60

Reason for abandonment of well or producing formation

COMPLETED AS A LOW MARGINABLE WELL & NO SALES LINE AVAILABLE

If a producing well is abandoned, date of last production NONE 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRED HAMPEL, PRETTY PRAIRIE, KANSAS

Producing formation MISS. CHERT Depth to top 4648' Bottom ----- Total Depth of Well 4735' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
MISS. CHERT	WATER & LITTLE	4652'	4666'		1057.43'	NONE
	GAS				4732'	3965'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

(PLUGGED BACK TO 4689')

FILLED HOLE WITH CRUSHED ROCK FROM 4689'-3980', FOLLOWED BY A PLUG. PLACED 5 SACKS OF CEMENT ON TOP OF PLUG. FILLED HOLE WITH HEAVY MUD TO 300' AND BUILT SOLID ROCK BRIDGE. PLACED 20 SACKS OF CEMENT ON TOP OF SOLID ROCK BRIDGE. FILLED HOLE WITH HEAVY MUD TO 35' AND BUILT SOLID ROCK BRIDGE. FILLED HOLE TO BASE OF WELL CELLAR WITH 10 SACKS OF CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
2-24-60
FEB 24 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor MORGAN WELL PLUGGING SERVICE

Address 102 WEST 18TH STREET, HUTCHINSON, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle

ROUTE 2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 22ND day of FEBRUARY, 19 60

My commission expires APRIL 14, 1963 Notary Public.



15-007-00613-0000
WELL LOG

COMPANY PETROLEUM, INCORPORATED

SEC. 9 T. 33S. ~~X4~~ 14W

FARM MC GRATH "B" NO. 1

LOC. NE, NE, SW


TOTAL DEPTH 4735'

COUNTY BARBER CO., KANSAS

COMM. March 8, 1958

COMP. March 25, 1958

CONTRACTOR GARVEY DRILLING COMPANY



CASING ~~XXXXXX~~ 8 5/8" @ 1057.43' W/500 sax.
4 1/2" @ 4732' W/125 sax.

ELEVATION 1761' DF

PRODUCTION MISSISSIPPIAN

FIGURES INDICATE BOTTOM OF FORMATIONS

360	Shale, clay & red bed
1060	Red bed & shale
1750	Shale & sand
2035	Shale & lime
2310	Lime
3015	Lime & shale
3100	Shale
3727	Lime & shale
3827	Shale
3990	Shale & lime
4103	Shale & sand
4133	Lime & shale
4655	Lime
4688	Chert & lime
4735	Lime
4735	T. D.

RECEIVED
STATE CORPORATION COMMISSION

FEB 24 1960
2-24-60
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING CO.

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 MC GRATH "B" well

Verne A. Morris

Subscribed and sworn to before me this 17th day of April 19 58

My Commission Expires: July 11, 1960

Ed J. Brown
NOTARY PUBLIC