

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Blitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Barber County. Sec. 30 Twp. 31 Rge. 11 XX (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NW

Lease Owner Solar Oil Company

Lease Name M. T. Williams Well No. 3

Office Address 1117 Union National Bank Bldg. Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 21, 1955

Application for plugging filed April 21, 1955

Application for plugging approved April 21, 1955


Plugging commenced April 21, 1955

Plugging completed April 21, 1955

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4321 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	213 $\frac{1}{2}$	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 4321 feet to surface feet for each plug set.

Pumped in heavy mud

Plug at 210 with 20 sacks cement

Plug at 35' with 10 sacks cement to base of cellar

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1955
4-26-55
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor D. & M. Drilling Company, Inc.
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.
James Davis, Jr., (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James Davis, Jr.
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of April, 1955
Leota Lee Miller
Leota Lee Miller Notary Public.

My commission expires July 27, 1955 23-8390-s 6-51-20M

PLUGGING
FILE SEC 30 T 31 R 11 W
BOOK PAGE 113 LINE 44

WILLIAMS #3

SW/4 SW/4 NW/4 of Section 30-31S-11W Barber County, Kansas

Rigged up Rotary Tools 4/4/55

Ran 7 JTS (213.35') 8 5/8" 32#
Casing set at 212'. Cemented with
200 Sacks Cement.

Tore down Rotary Tools 4/21/55

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand	0'	25'
Shale & shells	25	110
Redbed & shells	110	212
Shale & shells w/sand streaks	212	1030
Shale w/lime streaks	1030	1565
Shale & lime	1565	1680
Shale w/lime streaks	1680	1881
Lime	1881	1950
Shale w/lime streaks	1950	2016
Lime & shale	2016	2120
Lime w/shale streaks	2120	2270
Lime & shale	2270	2540
Sandy shale w/lime streaks	2540	2780
Shale & brown lime	2780	2910
Shale	2910	3015
Lime w/shale streaks	3015	3105
Lime	3105	3175
Lime & shale	3175	3283
Shale	3283	3350
Sand	3350	3375
Sand & shale	3375	3450
Lime & shale w/sand streaks	3450	3517
Lime, shale & sand	3517	3660
Lime & shale	3660	3724
Lime w/shale streaks	3724	3762
Lime	3762	4135
Lime w/shale streaks	4135	4181
Lime & shale	4181	4272
Mississippi Lime	4272	4282
Chat	4282	4292
Chert	4292	4321 TD


I, W. M. Barnett, do hereby certify that the foregoing log is true and correct, to the best of my knowledge and belief.

W. M. Barnett

Subscribed and sworn to before me this 22nd day of April, 1955

Jim Swaney

My Commission Expires: July 29, 1957



APR 26 1955
 4-26-55
 CONSERVATION DIVISION
 Wichita, Kansas