


15-007-10311-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 20 Twp. 33 Rge. (E) 15 (W)
CSE/4
Location as "NE/CNW/SW" or footage from lines _____
Lease Owner Barbara Oil Company
Lease Name McKee Heirs Well No. 7
Office Address 322 Central Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Gas
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 4-17 19 62
Plugging completed 4-23 19 62
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production Approx. Sept. 1 19 60
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Kampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4992 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	277'	None
				7"	4992"	3009"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug at 4886' - Top Perforation 4589'

Sanded hole to 4575' - dumped 5 sacks cement - pulled casing - bailed fluid down - set 10' rock bridge at 260' = mudded hole to 35' - set 10' rock bridge - dumped 15 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1962
5-22-62
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R&D Casing Pulling Co. Licence # 236
Address Box 572, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R.F. Ramsey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
R.F. Ramsey Landman
322 Central Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of May, 19 62

[Signature]
Mildred Fisher Notary Public.

My commission expires March 2, 1965



N 15-007-10311-0000

WELL LOG

BARBARA OIL COMPANY
McKee Heirs #7
CSE/4 Sec. 20-33S-13W
Barber County, Kansas

CASING RECORD
10-3/4" 277'
7" 4992' w/600 sacks

Elev. 1645'
Contractor: S.A. Springer
Commenced: December 26, 1941
Completed: March 19, 1942
IP: Est. 4 MCF

Sand - soil	0	8	Lime dark sandy	4090	4115
Red sticky clay	8	50	Lime hard	4115	4185
Red Rock	50	150	Lime	4185	4340
Gyp shell	150	160	Slate	4340	4360
Red bed	160	270	Lime	4360	4365
Red shale	270	340	Cherty lime (Core 4365-4379		
Red bed	340	745	trace dead oil)	4365	4370
Red rock-shale-shells	745	1060	Cherty lime hard at 4370		
Shale-Anhydrite	1060	1150	Lime hard	4379	4412
Shale-shells	1150	1400	Black lime	4412	4420
Shale-salt	1400	1550	Lime	4420	4430
Shale-lime	1550	1645	Shale	4430	4440
Salt-shale	1645	1700	Broken lime	4440	4460
Shale	1700	1750	Broken hard lime	4460	4465
Anhydrite-shale	1750	1810	Broken lime	4465	4475
Lime-shale	1810	2030	Black lime	4475	4485
Lime	2030	2045	Broken lime	4485	4500
Lime-shale	2045	2185	Shale	4500	4515
Conglomerate sticky	2185	2230	Lime (Top Miss. lime 4515)	4515	4535
Shale-lime	2230	2285	Shale	4535	4550
Lime	2285	2370	Chatty Conglomerate	4550	4565
Sticky shale	2370	2380	Chatty lime	4565	4585
Stickey shale-lime	2380	2490	Chatty lime chert shell 4588		
Lime	2490	2510	Chert	4595	4600
Lime-shale	2510	2630	Chatty lime-chert	4600	4610
Sticky shale	2630	2660	Green shale-chert-sand	4610	4625
Lime	2660	2675	Chatty lime-chert	4625	4630
Shale-lime	2675	2795	Green lime-sandy cong.	4630	4635
Sticky shale	2795	2835	Gas sand	4635	4638
Shale-lime	2835	2920	Gray shale	4638	4655
Shale	2920	3095	Cherty lime	4655	4660
Shale-lime	3095	3150	Lime	4660	4670
Lime	3150	3285	Shale	4670	4675
Broken lime	3285	3375	Brown cherty lime	4675	4680
Lime	3375	3485	Shale-lime	4680	4705
Shale	3485	3535	Shale sticky	4705	4762
Sticky shale	3535	3575	Lime brown hard	4762	4790
Shale	3575	3605	Shale-blue-gray	4790	4865
Shale-shells	3605	3720	Shale black	4865	4897
Shale	3720	3905	Broken lime	4897	4901
Lime	3905	3910	Lime	4901	4934
Lime-shale	3910	3925	Cherty lime hard	4934	4980
Lime	3925	3935	Broken lime	4980	4992
Lime-shale	3935	3945	7" O.D. set at 4992'		
Shale black sticky	3945	3990	Top Viola lime 4897'		
Broken lime-shale	3990	4004			
Broken lime (Top K.C.4004)	4004	4020			
Lime hard	4020	4090			

RECEIVED
STATE CORPORATION COMMISSION
MAY 22 1962
5-22-62
CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick

R.F. Ramsey (employee of owner) of the above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature)

R.F. Ramsey
R.F. Ramsey, Landman

Subscribed and sworn to before me this 17th day of May, 1962

My Commission expires March 2, 1965

Mildred Fisher
Mildred Fisher Notary Public