

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-007-10316-0000

API NUMBER ~~15-007-97091-TMR-KCC~~

LEASE NAME THOMPSON

WELL NUMBER A-2

3940 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 22 TWP. 33S RGE. 13W(E) or (W)

COUNTY BARBER

Date Well Completed 02/27/38

Plugging Commenced 09/12/90

Plugging Completed 09/13/90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Chevron U.S.A. Inc.

ADDRESS P.O. Box 36366 Houston, TX 77236

PHONE# (713) 561-3602 OPERATORS LICENSE NO. 4519

Character of Well GAS WELL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 09/13/90 (date)

by STEVE PFIEFER (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation MISSISSIPPI CHAT Depth to Top 4556 Bottom 4660 T.D. 4680

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
MISSISSIPPI CHAT	GAS	4556	4660	13"	269	NONE
				7"	4556	NONE
				5-1/2"	4524	4650 (LINER)

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
SET CIBP @ 4450'. TAG CIBP AND CIRCULATED HOLE FROM 4450' TO SURFACE W/9.0 ROTARY MUD.
MIXED AND PUMPED 35 SACKS CLASS 'A' AT 15.6 PPG - 30 SACKS THRU CIBP AND 5 SACKS ON TOP.
PERFED W/CASING GUN, 2 SPF, FROM 620-622. MIXED AND PUMPED 96 SACKS B-J LITE CEMENT.
CIRCULATED CEMENT TO SURFACE. LEFT 7" CASING FULL OF CEMENT FROM 620 TO SURFACE.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B. J. SERVICES License No. N/A

Address P. O. BOX 4442, HOUSTON, TEXAS 77210

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: CHEVRON U. S. A. INC.

STATE OF TEXAS COUNTY OF HARRIS, ss.

SHARON L. HOUK (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


Signature Sharon L. Houk

* Note that old API number may be referred to as 15-007-10316.
 (Address) P. O. BOX 36366, HOUSTON, TX 77236

SUBSCRIBED AND SWORN to before me this 18 day of JANUARY, 19 91

Sharon A. Sweeney
 Notary Public

My Commission Expires NOVEMBER 21 1994



RECEIVED
 STATE CORPORATION COMMISSION
 JAN 22 1991
 1-22-91
 CONSERVATION DIVISION
 Wichita, Kansas