

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 South Market Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R. 82-3-117

15-007-10315 - 00-01  
API NUMBER Drilled 1932

LEASE NAME McKee

WELL NUMBER #5

1320 Ft. from N/S Section Line

3960 Ft. from E/W Section Line

SEC. 21 TWP. 33S RGE. 13 (XXXX) (W)

COUNTY Barber

Date Well Completed \_\_\_\_\_

Plugging Commenced 11/20/99

Plugging Completed 11/23/99

RECEIVED  
KANSAS CORP COMM  
12-3-99  
1999 DEC -3 12:24

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 60 days.

LEASE OPERATOR Herman Loeb

ADDRESS P.O. Box 524, Lawrenceville, IL 62439

PHONE# 812 853-3813 OPERATORS LICENSE NO. 3273

Character of Well Good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/22/99 (date)

by Steve Durant (KCC District Agent's Name)

is ACO-1 filed? yes If not, is well log attached? no

Producing Formation Snyderville & Douglas Depth to Top 3922-36 Bottom 3980-90 T.D. 4400 retainer

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				10 3/4	286	None
				7"		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Perf snyderville and test, perf douglas and test, pull tubing and packer, run 2 7/8 tubing to 4020, load hole with KCL water, spot 30sx cement 60/40, 6% jel, pull tubing to 600, circulate cement to surface with 95sx, 60/40 6% jel, lay down tubing, top 7" off with cement

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, 107 W. Fowler, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Herman Loeb

STATE OF Kansas COUNTY OF Barber, ss.

Alan Vratil (Employee of Operator) or (Operator) of above described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Alan Vratil

(Address) Medicine Lodge, KS 67104

SUBSCRIBED AND SWORN TO before me this 30 day of November, 19 99

Glenda Morrison  
Notary Public

My Commission Expires: 11/30/04

