

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 207B  
Wichita, KS 67202

K.A.R.-82-3-117

API NUMBER 15-007-21,422-00-00

LEASE NAME Spicer

WELL NUMBER 2

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 27 TWP. 30S RGE. 12W (E) or (W)

COUNTY Barber

LEASE OPERATOR VESS OIL CORPORATION

ADDRESS 8100 E. 22nd. N. Bldg. 300 Wichita, Kansas 67226

PHONE# (316) 682-1537 OPERATORS LICENSE NO. 5030

Date Well Completed         

Character of Well Oil

Plugging Commenced 6-16-00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-20-00

The plugging proposal was approved on          (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.O. 4657'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

RECEIVED

STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	333'	None
				4-1/2"	4645'	3200'

CONSERVATION DIVISION  
Wichita, Kansas

JUN 14 2000

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material was used, state the character of same and depth placed, from          feet to          feet each side. Plugged off bottom with sand to 3620' and 4 sks cement Shot pipe @3200', pulled up to 700', pumped 10 sks. gel and 50 sks. cement, pulled to 360', pumped 40 sks cement, pulled to 40', pumped 25 sks. cement to surface. 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil CORPORATION

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 11th day of July, 2000

[Signature]  
Notary Public

My Commission Expires:         

IRENE HERZBERG  
State of Kansas  
My Appt. Exp. Aug. 24, 2001

[Signature]  
Notary Public