


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 17 Twp. 30s Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW SE NE

Lease Owner Clair Gillin
Lease Name Lucky Kumburg Well No. 1
Office Address P.O. Box 5247, Kansas City, Missouri 64112
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 2 19 69
Application for plugging filed May 6 19 69
Application for plugging approved May 2 19 69
Plugging commenced May 2 19 69
Plugging completed May 2 19 69
Reason for abandonment of well or producing formation No Productible formation

If a producing well is abandoned, date of last production - - - - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph J. Warren
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	252	8 5/8	252	---

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Gunned pits forming heavy mud, filled hole up to 240 feet with mud. Pushed wooden plug and one half sack of hulls to 240 feet. Capped with 25 sacks of cement. Filled hole up to 40 feet. Capped with 10 sacks cement into base of well cellar. Pushed wooden plug and one half sack of hulls to 40 feet. Plugged rat hole and mouse hole with 2 sacks cement in each. Job complete at 3:00 P.M. 5-2-69.

RECEIVED
STATE CORPORATION COMMISSION
MAY 7 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address Box 261, Great Bend, Kansas 67539

STATE OF Kansas, COUNTY OF Barton, ss.
Verne A. Morris (Acting Agent) (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Verne A. Morris
Box 261, Great Bend, Kansas 67530
(Address)

Subscribed and Sworn to before me this 6th day of May 19 69
Richard Bays
Notary Public.

My commission expires November 5, 1969

WELL LOG


COMPANY Clair Gillin
FARM Lucky Kumburg NO. 1
TOTAL DEPTH 4544'
COMM. 4-23-69 COMP. 5-2-69
CONTRACTOR Garvey Drilling Company

SEC. 17 T. 30S. R. 12W

LOC. NW SE NE

COUNTY Barber, Kansas

CASING
8 5/8" @ 252' w/225sx



ELEVATION

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

50' Soil & Sand
252' Red Bed & Shale
255' Red Bed
1020' Red Bed & Shale
1880' Lime & Shale
2125' Lime
2305' Lime & Shale
3956' Lime, Chalk & Shale
4027' Lime
4265' Lime & Shale
4300' Lime
4371' Shale & Lime
4420' Lime & Shale
4544' RTD

RECEIVED
STATE CORPORATION COMMISSION
MAY 7 1969
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } SS

I, Charlene Marker of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the #1 Lucky Kumburg well.

Charlene Marker

Subscribed and sworn to before me this 6th day of May 1969

My Commission Expires: November 5, 1969

Richard Stoy
NOTARY PUBLIC