

15-007-21445-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Barber SEC. 18 TWP. 30S RGE. 12W ~~SW~~/W
 Location as in quarters or footage from lines:
C SE SE

Lease Owner F. G. Holl
 Lease Name Young #2-18 Well No. 2-18
 Office Address 6427 East Kellogg, Wichita, Kansas 67207
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed May 14, 1982
 Application for plugging filed May 14, 1982
 Plugging commenced 6:00 AM May 14, 1982
 Plugging completed 8:15 AM May 14, 1982
 Reason for abandonment of well or producing formation Dry Hole

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation _____ Depth to top _____ bottom T.D. 4730'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	295'	None

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Filled hole with heavy mud.
 Heavy mud to 750' with 60 sacks through open ended drill pipe
 at 750'; heavy mud to 285' with 40 sacks at 285'; through
 open ended drill pipe; heavy mud to 40' with 10 sacks to
 surface; 10 sacks in rathole and 5 sacks in mousehold.
 Cemented with Regular Cement with 2% gel and 3% cc.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY

(Signature) F. A. Wuellner
F. A. Wuellner, Sterling, Ks 67579
 (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of May, 1982.



Agnes D. Wurst
 Agnes D. Wurst, Notary Public.

My Commission expires: _____

RECEIVED
 STATE CORPORATION COMMISSION

MAY 17 1982

CONSERVATION DIVISION
 Wichita, Kansas

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - YOUNG #2-18

Located: C SE SE, Section 18-30S-12W, Barber County,
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 5, 1982

COMPLETED: May 14, 1982

TOTAL DEPTH: 4730'

LOG

0 - 41 Sand
41 - 298 Red Bed
298 - 1530 Shale
1530 - 4355 Lime and Shale
4355 - 4445 Lime
4445 - 4565 Lime and Shale
4565 - 4650 Lime
4650 - 4730 Lime and Shale

CASING RECORD

Ran 7 joints new 8 5/8", 23# casing.
283.34' pipe set at 295' K.B. Cemented
with 225 sacks 60/40 Pozmix with 2% gel
and 3% cc. Plug down at 4:00 PM,
5-5-82, by Howco.

Plugged.

Deviation Surveys: 1° at 1939'
3/4° at 4324'
3/4° at 4730'

RECEIVED
STATE CORPORATION COMMISSION

MAY 17 1982

CONSERVATION DIVISION
Wichita, Kansas