

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-20,226A

LEASE NAME Cook #1-18

WELL NUMBER \_\_\_\_\_

SPOT LOCATION C NW NW

SEC. 18 TWP. 30s RGE. 12w (E) or (W)

COUNTY Barber

Date Well Completed \_\_\_\_\_

Plugging Commenced 2/29/84

Plugging Completed 3/5/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR F.G. Holl

ADDRESS 6427 E. Kellogg, Wichita, Ks. 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. #5056

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4616'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	285'	none
				4 1/2"	4659'	3114'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Pumped bottom with 40 sacks cement to 3800'. Shot pipe at 3300' & 3120'.

Pulled 76 joints of pipe. Plugged well with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, plug, & 125 sacks 60/40 poz 2% gel 3% c.c.

Plugging complete

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

RECEIVED  
STATE CORPORATION COMMISSION

MAR 12 1984

SUBSCRIBED AND SWORN TO before me this 9th day of March, 1984

CONSERVATION DIVISION  
Wichita, Kansas  
My Comm. Expires \_\_\_\_\_



Irene Hoover  
Notary Public