


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Happer County, Sec. 4 Twp. 33 Rge. 7 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE SE NW
Lease Owner Sinclair Oil & Gas Co.
Lease Name Anna B. Stewart #1 Well No. _____
Office Address Chase, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Exhausted Oil Well
Date well completed 3/21/56 19____
Application for plugging filed February 26 1959
Application for plugging approved March 3 1959
Plugging commenced 3-7-59 19____
Plugging completed 3-11-59 19____
Reason for abandonment of well or producing formation Oil depleted to point where well unprofitable to operate.
If a producing well is abandoned, date of last production December 31 1958
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Fred Hample
Producing formation Misener Sand Depth to top 4545 Bottom 4853 Total Depth of Well 5065 Feet
Show depth and thickness of all water, oil and gas formations. PBID 4895

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Misener Sand</u>	<u>Oil & Water</u>	<u>4845</u>	<u>4853</u>	<u>10-3/4"</u>	<u>274'</u>	<u>none</u>
				<u>5-1/2"</u>	<u>4930'</u>	<u>4112'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 4865' and found it open. Filled w/sand to 4830' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" casing, cleared hole and checked fluid to 260', mud to 250', set rock bridge to 240' and dumped 25 sacks of cement. Mudded the hole to 40', set rock bridge to 30' and ran 15 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1959
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
I, Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 14 th day of March, 1959

My commission expires 9-27-62 Thomas V. Dwyer Notary Public.

PLUGGING
FILE SEC. 4 T. 33 R. 7 W
BOOK PAGE 18 LINE 41


WELL LOG BUREAU - KANSAS GEOLOGICAL SURVEY
508 East Missouri
White, Kansas

Company - SINCLAIR OIL & GAS
Farm - Anna B. Stewart No. 1

SEC. 4 T. 33 R. 7W
NE SE NW

Total Depth. 5065'
Comm. 2-14-56 Comp. 3-14-56
Shot or Treated.
Contractor. Gabbert-Jones Drilg.
Issued. 5-19-55

County Harper
KANSAS



CASING:
10 3/4" 274' ccm w/200 sx

Elevation. 1362'

Production. 237 BOPD

Figures indicate Bottom of Formations.

red bed & shale	95
red bed	274
red bed & shale	900
salt	960
shale	1200
shale & anhydrite	1225
anhydrite	1260
shale, shells & lime	1415
lime	2060
shale & broken lime	2135
lime & shale	2270
sandy shale	2405
shale & shells	2985
lime	3040
shale & shells	3100
sandy shale	3160
shale & lime	3445
shale & shells	3620
sand	3758
sand & shale	3880
lime	3960
lime & shale	3987
lime	4060
lime & shale	4100
lime	4151
shale & lime	4295
lime	4335
shale & lime	4410
shale	4464
shale & lime	4474
lime	4505
shale & lime	4725
lime	4737
shale	4790
shale & shells	4825
shale	4845
sand	4859
sand & dolomite	4889
sand	4958
sandy shale	5052
lime & shale	5065
Total Depth	

Tops: Scout	
Oread	3274
Hoebner	3265
Stalmaker	3590
Kansas City	3893
Mississippi	4443
Kinderhook	4748
Nisner Sand	4846
Viola	4855
Simpson Dolomite	4872
Arbuckle	5039