

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

x			

Locate well correctly on above  
Section Plat

Barber County. Sec. 19 Twp. 33S Rge. 13W (E) \_\_\_\_\_ (W) \_\_\_\_\_  
 Location as "NE/CNW&SWK" or footage from lines NW NW NW  
 Lease Owner Mill Drilling Co. Inc.  
 Lease Name Mahan-Tarr Well No. 2  
 Office Address Same as above.  
 Character of Well (completed as Oil, Gas or Dry Hole) oil well.  
 Date well completed March 1956 19 62  
 Application for plugging filed Jan. 29 19 62  
 Application for plugging approved Jan. 29 19 62  
 Plugging commenced Jan. 29 19 62  
 Plugging completed Feb. 3 19 62  
 Reason for abandonment of well or producing formation \_\_\_\_\_  
Prod. drop.  
 If a producing well is abandoned, date of last production 1-15 19 62  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
 Producing formation Miss and Warm. Depth to top 4659 Bottom 4649' Total Depth of Well 4690' Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Killed well sanded from 4690' to 4630' dumped 4 sax. cement. Shot pipe off at 3704 and pulled same. Mudded hole to 190' 10" rock bridge set, dumped 20 sax cement. Mud to 40' set 10' rock bridge and dumped 10 sax cement. This completed plugging.

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 FEB 23 1962  
 CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Ralph Comstock pipe pulling Inc.  
 Address Stafford, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Joseph O. Butts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph O. Butts "Fred. Dept"  
Wichita, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of February, 1962

Better H. Salter  
 Notary Public.

My commission expires October 16, 1965

*File*

**ROTARY DRILLERS LOG**

COMPANY : Mull Drilling Company, Inc. ROTARY DRILLING COMMENCED: 3-9-56  
 Wichita, Kansas

CONTRACTOR : Mull Drilling Company, Inc. ROTARY DRILLING COMPLETED: 3-23-56  
 Wichita, Kansas

CASING RECORD : Set 8 5/8" @ 200' cemented LOCATION: NW NW NW - MAHAN-TARR #2  
 with 175 sacks cement. Sec. 19-31S-1W  
 Barber County, Kansas

Set 5 1/2" @ 4690' cemented  
 with 150 sacks cement.

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

Sand	50	Lime & Shale	4202
Red Rock	200	Lime	4690' R.T.D.
Red Bed & Shells	1095		
Shale & Shells	1900		
Lime	2010		

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

*[Signature]*  
 BY J. A. MULL, JR., PRESIDENT

STATE OF KANSAS }  
 COUNTY OF SEDGWICK } SS

Subscribed and sworn to before me this 26th day of March, 1956.



*E. Zimmerman*  
 NOTARY PUBLIC

RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB 27 1956  
 2-23-62

MY COMMISSION EXPIRES: JANUARY 28, 1957.