


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Harper County, Sec. 18 Twp. 33S Rge. 7 ~~E~~/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
660' FNL and 1980' FWL  
Lease Owner R. Clark Taylor Exploration, Inc.  
Lease Name King Well No. 18-A  
Office Address Suite 480, City Center, Okla. City, Okla. 73101  
Character of Well (Completed as Oil, Gas or Dry Hole)  
Dry Hole  
Date Well completed October 24, 1982  
Application for plugging filed October 24, 1982  
Application for plugging approved October 24, 1982  
Plugging commenced October 24, 1982  
Plugging completed October 24, 1982  
Reason for abandonment of well or producing formation



Locate well correctly on above  
Section Plot

If a producing well is abandoned, date of last production  
19  
Was permission obtained from the Conservation Division or  
its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Maurice V. Leslie, Nashville, Ks.  
Producing formation Depth to top Bottom Total Depth of Well 4625  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	258'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- 1st plug @ 800' with 60 sacks
- 2nd plug @ 300' with 40 sacks
- 3rd plug @ 60' with 20 sacks
- plugged rat hole with 10 sacks

RECEIVED  
STATE CORPORATION COMMISSION

NOV 09 1982

CONSERVATION DIVISION  
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Betty Brandt (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Betty Brandt  
910 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of October, 19 82



Tricia K. Glidewell  
Notary Public.

My commission expires March 16, 1986

RECEIVED  
STATE CORPORATION COMMISSION

NOV 09 1982

CONSERVATION DIVISION  
Wichita, Kansas

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR R. Clark Taylor Explor., Inc. LEASE King 18-A SEC. 18 TWP. 33S RGE. 7W

**FILL IN WELL LOG AS REQUIRED:**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Red bed	0	778		
Red bed & shale	778	1477		
Shale	1477	1882		
Shale & lime	1882	4550		
Lime & shale	4550	4625		
Rotary Total Depth		4625		

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 09 1982  
CONSERVATION DIVISION  
Wichita, Kansas

**Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)**

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	23#	258'	common	175 sx.	2% Gel, 3% CC

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

Size	Setting depth	Packer set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**