


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Harper _____ County, Sec. 12 Twp. 33S Rge. _____ (W)
Location as "NE/CNW&SWK" or footage from lines 2310 fr N, 330 fr W, NW/4
Lease Owner Phillips Petroleum Company
Lease Name Sturns "A" Well No. 1
Office Address Box 779, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 7, 19 55
Application for plugging filed December 8, 19 55
Application for plugging approved December 9, 19 55
Plugging commenced December 8, 19 55
Plugging completed December 8, 19 55
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives, Box 8, Pratt, Kansas
Producing formation Dry Hole Depth to top _____ Bottom _____ Total Depth of Well 4977 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Lansing-Kansas City	Dry	3949	4156	9-5/8"	250.59'	None
Marmaton	Dry	4234	4390			
Cherokee	Dry	4390	4489			
Mississippian	Dry	4489	4799			
Kinderhookian	Dry	4799	4859			
Chattanooga	Dry	4859	4887			
Misener-Viola	Dry	4887	4936			
Simpson	Dry	4936	4977			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole from 4977' to 250'. Set 9-5/8" plug at 250', dumped 20 sx. cement to 190'. Filled with mud from 190' to 40'. Set 9-5/8" plug at 40'. Dumped 15 sx. cement from 40' to base of cellar. Well plugged and abandoned at 6:00 P.M. 12-8-55.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Carvey Drilling Company
Address Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
A. J. Willis (employee of owner) ~~PRODUCER/OPERATOR~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 779, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of December, 19 55

My commission expires November 18, 1957

[Signature] Notary Public.

24-7368-S 3-53-20M

RECORDED
STATE COMMISSION
12-13-55
DEC 13 1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 12 T. 38 R. 8W
BOOK PAGE 22 LINE 32

EXPLORATION RECORD

Phillips Petroleum Company - Sturns "A" #1 - Dry Hole
 2310' from North and 330' from West lines, NW/4 Sec. 12-33S-8W, Harper County, Kansas

Lease Sturns "A"

Well 1

Formation Name	Top	Base	Remarks
Surface sand and clay	0	310	
Shale and shells	310	760	
Lime, chert and shale	760	1525	
Shale	1525	1980	
Lime and shale	1980	2870	
Shale	2870	3100	
Lime and chert	3100	3327	
Shale	3327	3880	
Lime and shale	3880	4012	
Lime	4012	4558	
Lime and shale	4558	4600	
Mississippian	4600	4672	
Lime and shale	4672	4749	
Lime and chert	4749	4787	
Lime and shale	4787	4820	
Shale	4820	4885	
Sand	4885	4892	
Sand and shale	4892	4897	
Lime	4897	4950	
Sand	4950	4977	
FORMATION TOPS:			
Stalnaker	3682		
Kansas City	3949		
Base-Kansas City	4156		
Marmaton	4234		
Cherokee	4390		
Mississippian	4489		
Kinderhookian	4799		
Chattanooga	4859		
Misener-Viola	4887		
Simpson Shale	4936		
Simpson Dolomite	4938		
Simpson Sand	4949		
Total Depth	4977		

RECORDED
 NOV 17 1955
 HARPER COUNTY, KANSAS

PLUGGING
 FILE SEC 12 T 33 R 8 W
 BOOK PAGE 22 LINE 37