


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Harper _____ County, Sec. 1 Twp. 34S Rge. 7 (W)
Location as "NE/CNW&SW" or footage from lines G: NW $\frac{1}{4}$, NW $\frac{1}{4}$, NW $\frac{1}{4}$
Lease Owner Gulf Oil Corporation
Lease Name C. E. Birchenough Well No. 1
Office Address Box 661, Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-21 19 54
Application for plugging filed 10-25- 19 54
Application for plugging approved 10-22 19 54
Plugging commenced 10-23- 19 54
Plugging completed 10-24 19 54
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production -0- 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Arbuckle Depth to top 5194' Bottom 5215' Total Depth of Well 5215' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	250'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Displaced mud in upper half of hole with heavy mud from pits to 240' of surface. Set HOWCO plug at 240' capped with 1/2 sx hulls. Spotted 20 sx Monarch Portland cement furnished by HOWCO. Filled hole with mud to 20' of surface and set HOWCO plug with 1/2 sx hulls. Filled hole to bottom of cellar with 10 sx of Monarch Portland cement furnished by HOWCO.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barbour Drilling Co.
Address 717 First National Bank Bldg., Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Rice, ss.
W. H. Duley (employee of owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. H. Duley
Box 544, Chase, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 27th day of October, 1954

My commission expires April 14, 1953
W. M. Council Notary Public.

24-7368-8 3-53-20M

PLUGGING

FILE SEC LT 34 R 7W
BOOK PAGE 22 LINE 31

10-26-54
:bng

WELL RECORD

GULF T 880-A PRINTED IN U.S.A.

WELL NO. **1** LEASE **C. E. Birchborough** COMPANY **Gulf Oil Corporation** A.F.E. **3326 (35-W)**

DATE—DRILLING BEGAN **9-15-54** ~~WELL~~ ^{Plugging} COMPLETED **10-23-54** FIRST PRODUCTION **Dry**

SAND RECORD **Dry Hole - Plugged & Abandoned** TOTAL DEPTH **5215'**

INITIAL PRODUCTION

CASING RECORD

SIZE	WEIGHT	THD.	CLASS	MAKE	SET AT DEPTH	SACKS CEMENT	LES. CAL. CHLO.	PULLED	LEFT IN
10-3/4	*	*	A	*	249	175			249
NOTE: * 4jts-32.75" - SR - SS 3jts-29" - RT - SH									

S- 2 T- 3HP- 7W

0											Center
											SH
											SH
											SH
											Harper
											County
											Kansas

Distance R: 12' from RKB to top of 10-3/4" coghead flange. ELEVATION— DP 1298'

Cemented bottom of hole w/50 sacks cement, then 40 sacks cement @ 374'.

Formation Record

	From	To
Surface	0	120
Sd, sh		230
Sh		525
Rd bd, sh		1150
Sh, lm		1805
Ln		1960
Sh, lm		2355
Sh		2490
Sh, lm		3495
Ln		3505
Sh, lm		3660
Sh, shells		3772
Sh		3825
Sh, lm		3922
Ln		4430
Sh		4509
Sh, lm		4555
Ln		4658
Chert, lm		4731
Ln		4828 4822
Sh, lm		4928
Sh		4955
Sd		5095
Sd, sh		5121
Sh		5162
Sd		5167
Sd, sh		5215' TD

STATE OF KANSAS
NOV 19 1954
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC LT 34 R 7W
BOOK PAGE 72 LINE 21