


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Harper County. Sec. 30 Twp. 34S Rge. 6N (E) (X)  
Location as "NE/CNW/SW" or footage from lines SW/4 of SW/4 of SE/4  
Lease Owner J. M. Huber Corporation  
Lease Name M. E. Reneau Well No. 1  
Office Address Box 978 Liberal, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 9 19 58  
Application for plugging filed May 8 19       
Application for plugging approved      19       
Plugging commenced May 9 19 58  
Plugging completed May 9 19 58  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production - 19       
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Fred Hample  
Producing formation none Depth to top - Bottom - Total Depth of Well 5260 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9-5/8"	337'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Pushed plug to 235' w/1/3 sacks hulls. Cemented thru drill pipe w/20 sacks pozmix. Filled w/mud to 40'. Spotted plug w/1/3 sacks hulls at 40'. Cemented to top w/10 sacks cement. Plugging supervised by Mr. Fred Hample, state plugger.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. M. Huber Corporation  
Address Box 978 Liberal, Kansas

STATE OF Kansas, COUNTY OF Seward, ss.  
W. W. Henson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Henson  
Box 978 Liberal, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of May, 1958

My commission expires 5-1-61

Frederick Garcia  
Frederick Garcia  
Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 20 1958

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 30 T 34R 6W  
BOOK PAGE 102 LINE 1

WELL LOG

WELL NAME: M. E. Reneau #1  
WELL LOCATION: 330' from south line, 3045' from east line. SW/4 of SW/4 of SE/4 of Section 30, Township 34S, Range 6N, Harper County, Kansas.  
WELL OWNER: J. M. Huber Corporation  
DRILLING COMMENCED: 4-15-58  
DRILLING COMPLETED: 5-9-58  
WELL COMPLETED: 5-9-58  
TOTAL DEPTH: 5260'

<u>FORMATION</u>	<u>DEPTH</u>
Red bed, shells	0 - 337
Red bed	337 - 595
Shale, shells	595 - 1270
Lime, shale	1270 - 1567
Lime	1567 - 1585
Lime, shale	1585 - 2861
Shale	2861 - 2918
Shale, lime	2918 - 3822
Lime	3822 - 4357
Lime, shale	4357 - 4447
Lime	4447 - 4655
Lime, chert	4655 - 4700
Cherty lime	4700 - 4760
Chert	4760 - 4774
Cherty lime, shale	4774 - 4784
Cherty lime	4784 - 4888
Cherty lime, lime	4888 - 4907
Cherty lime	4907 - 5069
Cherty lime, shale	5069 - 5078
Chert stringers, shale	5078 - 5092
Shale-lime	5092 - 5099
Shale	5099 - 5238
Lime, sand	5238 - 5248
Sand	5248 - 5260

STATE OF KANSAS, COUNTY OF SEWARD, ss

W. W. Henson, employee of owner of the above-described well, being first duly sworn on oath, says: That I have knowledge of facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct.

*W. W. Henson*

W. W. Henson

Subscribed and sworn to before me this \_\_\_\_\_ day of May, 1958,

*Frederick Garcia*

Frederick Garcia  
Notary Public

PLUGGIN  
FILE SEC 30 T 34 R 6W  
BOOK PAGE 102 LINE 1