


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

HARPER County, Sec. 30 Twp. 34S Rge. (E) 6 (W) (W)
Location as "NE/CNW%SW%" or footage from lines APPROX. C SW NE
Lease Owner BEN J. TAYLOR
Lease Name DENTON Well No. 1
Office Address 2809 NW EXPRESSWAY, OKLAHOMA CITY, OKLAHOMA
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 11-7- 19 66
Application for plugging filed (PHONE 11-7-66) 11-9- 19 66
Application for plugging approved 11-7- 19 66
Plugging commenced 11-7- 19 66
Plugging completed 11-7- 19 66
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5230 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	297	8-5/8"	297'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 280 FEET. SET ONE SACK DRY CEMENT, PLUG, 24 SACKS CEMENT ON TOP OF PLUG. FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET 1/2 SACK DRY CEMENT, PLUG, 9 SACKS CEMENT ON TOP OF PLUG. PLUGGED RAT HOLE WITH 2 SACKS CEMENT. JOB COMPLETE @ 9:00 AM, NOVEMBER 7, 1966.

NOV 10 1966
11-10-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GABBERT-JONES, INC.
Address 830 SUTTON PLACE, WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
E. E. HALL (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall
830 SUTTON PLACE, WICHITA, KANSAS 67202
(Address)

SUBSCRIBED AND SWORN to before me this 9TH day of NOVEMBER, 19 66

My commission expires FEBRUARY 1, 1968

Barbara J. Layton
BARBARA J. LAYTON
Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

DENTON #1
 APPROX. C SW NE SECTION 30-34S-6W
 HARPER COUNTY, KANSAS

COMMENCED: OCTOBER 22, 1966
 COMPLETED: NOVEMBER 7, 1966

OPERATOR - BEN J. TAYLOR

DEPTH		FORMATION	REMARKS
FROM	TO		
0	20	CLAY	
20	297	RED ROCK AND SHALE	RAN 13 JOINTS OF 8-5/8" CASING, SET @ 297' w/250 SACKS CEMENT.
297	450	RED BED	
450	1140	RED BED AND SHALE	
1140	1155	ANHYDRITE	
1155	1295	LIME AND SHALE	
1295	1465	LIME	
1465	2810	LIME AND SHALE	
2810	2930	SHALE	
2930	3010	SAND AND SHALE	
3010	3405	SHALE AND LIME	
3405	3480	SHALE AND SAND	
3480	3670	SHALE AND SHELLS	
3670	3715	SHALE AND LIME	
3715	3859	SAND AND SHALE	
3859	4000	LIME AND SHALE	
4000	4230	LIME	
4230	4435	LIME AND SHALE	
4435	4480	LIME	
4480	4678	LIME AND SHALE	
4678	4985	LIME	
4985	5140	LIME AND SHALE	
5140	5205	SHALE	
5205	5230	SAND	
5230	TD		DRY AND ABANDONED.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE APPROX. C SW NE SECTION 30-34S-6W, HARPER COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 8TH DAY OF NOVEMBER, 1966, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton

 BARBARA J. LAYTON, NOTARY PUBLIC

My COMMISSION EXPIRES FEBRUARY 1, 1968.