

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-211620001

LEASE NAME Whisman

WELL NUMBER 1

650 Ft. from S Section Line

760 Ft. from E Section Line

SEC. 19 TWP. 34 RGE. 6 ~~CDSE~~ (W)

COUNTY Harper

Date Well Completed _____

Plugging Commenced 4-23-97

Plugging Completed 4-24-97

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

Copy

LEASE OPERATOR L & J Oil Properties, Inc.

ADDRESS 150 N. Main, Suite 1026, Wichita, KS 67202

PHONE#(316) 269-3432 OPERATORS LICENSE NO. 31484

Character of Well good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4-23-97 (date)

by Woorly (KCC District Agent's Name).

Is ACO-1 filled? yes If not, is well log attached? yes

Producing Formation Miss Depth to Top 4672 Bottom 4700 T.D. 4837

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	217	None
				4 1/2	4865	3700

REC'D
KANSAS
APR 30 1997
12

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from feet to feet each section. Sand well back to 4605, dump 4sx portland cement with dump bailor, stretch and cut pipe at 3700, pull casing to 1210 and spot 35sx cement, pull casing to 814 and spot 35sx cement, pull casing to 276, circulate cement to surface, lay down the rest of casing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: L & J Oil Properties, Inc.

STATE OF Kansas COUNTY OF Barber, ss.


Alan Vratil

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances stated herein and the log of the above-described well as filed therewith, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Medicine Lodge, KS 67104



SUBSCRIBED AND SWORN TO before me this 25 day of April, 1997

Glenda Morrison
Notary Public

My Commission Expires: 10/14/98