


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Harper County, Sec. 23 Twp. 34S Rge. (E) 7 (W)
Location as "NE/CNW/SW" or footage from lines: C NW SE
Lease Owner: Pickrell Drilling Company
Lease Name: Bouse "A" Well No. 1
Office Address: 705 4th Nat'l Bank Bldg., Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole
Date well completed: February 7, 1969
Application for plugging filed: February 7, 1969
Application for plugging approved: February 7, 1969
Plugging commenced: February 7, 1969
Plugging completed: February 7, 1969
Reason for abandonment of well or producing formation: Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Archie V. Elving, Pratt, Kansas
Producing formation: _____ Depth to top: _____ Bottom: _____ Total Depth of Well: 5150 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	255'	None


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 240'. Set plug. Cemented with 25 sacks cement.
Heavy mud to 40'. Set plug. Cemented with 10 sacks cement
to bottom of cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 21 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: Pickrell Drilling Company
Address: 705 Fourth National Bank Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (owner or operator) of the above-described well, being duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) L. M. Whiting
W. Sebitts, Partner & Attorney-in-Fact
705 4th Nat'l Bank Bldg., Wichita, Ks. 67202
(Address)

Subscribed and sworn to before me this 14th day of February, 1969.
My commission expires May 10, 1970
L. M. Whiting Notary Public.

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
 705 Fourth National Bank Bldg.
 Wichita, Kansas 67202
 Rotary Drilling Commenced 1-22-69
 Rotary Drilling Completed 2-7-69

LOCATION: Bouse "A" No. 1
 C NW SE Sec. 23-34S-7W
 Harper County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (13 jts.) 8 5/8" surface casing set at 255' KB cemented with 160 sacks cement. Circulated. Completed @ 5:30 PM, January 22, 1969. No oil string run. D. & A., plugged February 7, 1969.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

255	Red Rock	C. F. S.
750	Red Bed & Shale	4060
1245	Shale & Shells	4695
1290	Anhydrite	5072
1640	Shale & Shells	5082
1670	Lime	5100
1885	Lime & Shale	5106
2035	Lime	5112
3770	Shale & Lime	5150
3840	Sand	
3875	Shale & Lime	
3925	Sand & Shale	
4020	Shale & Lime	Slope Tests
4470	Lime	3000
4655	Lime & Shale	3500
4671	Mississippi	4000
4695	Chert	4500
4740	Mississippi	5000
4845	Lime & Chert	
4934	Lime	
4975	Shale & Lime	
5100	Lime & Shale	S. L. M.
5106	Sand	
5150	Simpson, RTD	4363'

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 21 1969
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By [Signature]
 C. W. Sebitts, Attorney-in-Fact

STATE OF KANSAS
 COUNTY _____

ss.:

On _____ of February, 19 69, before me the undersigned, a Notary Public, in and for the County of _____ said, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact. He acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

and seal of office the day and year last above written.

My commission expires: May 10, 1970

[Signature]
 Notary Public
 L. M. Whiting

