


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Harper County. Sec23 Twp34 Rge. (E) 7 (W)
Location as "NE/CNWxSWx" or footage from lines NE SE NE
Lease Owner Home-Stake Oil & Gas Co.
Lease Name Orr Well No. 1
Office Address 507 Philtower Bldg. Tulsa, Okla. 74103
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 3 19 70
Application for plugging filed December 3 19 70
Application for plugging approved December 3 19 70
Plugging commenced December 2 19 70
Plugging completed December 3 19 70
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5150 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Red Bed		0	290	8-5/8"	282'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with heavy mud to 270'. Set plug with 1/2 sack hulls and 25 sacks cement through drill pipe.
Filled with heavy mud to 40' and set second plug with 1/2 sack hulls and 10 sacks cement.
Bridged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 14 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Gabbert-Jones, Inc.
Address 830 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
James S. Sutton, II (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James S. Sutton
830 Sutton Place, Wichita, Kansas 67202
(Address)



Subscribed and sworn to before me this 9 day of December, 1970
Barbara J. Layton
Barbara J. Layton Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

ORR #1
 NE SE NE Section 23-34S-7W
 Harper County, Kansas

Commenced: November 16, 1970
 Completed: December 3, 1970

OPERATOR - Home-Stake Oil & Gas Co.

DEPTH	FORMATION	REMARKS
From	To	
0	297	Red bed and shale
297	992	Shale and shells
992	1240	Sand and shale
1240	1500	Salt, shale and sand
1500	1655	Shale and shells
1655	3825	Shale and lime
3825	4080	Lime and shale
4080	4970	Lime
4970	4998	Shale
4998	5065	Lime and shale
5065	5144	Lime
5144	5150	Simpson Sand
5150	TD	Dry and abandoned.

Ran 8 joints of 8-5/8" casing, set @ 290' with 200 sacks cement.

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 14 1970
 CONSERVATION DIVISION
 Wichita, Kansas

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Well Log for the well drilled in the NE SE NE Section 23-34S-7W, Harper County, Kansas, to the best of my knowledge and belief.

James S. Sutton, II

 JAMES S. SUTTON, II

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State on this 9th day of December, 1970, personally appeared James S. Sutton, II, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

Barbara J. Layton

 Barbara J. Layton, Notary Public

My Commission Expires Feb. 1, 1972.

