

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Harper County. Sec. 14 Twp. 34E Rge. 7 (E) 7 (W)

Location as "NE/CNWSW" or footage from lines NE 1/4

Lease Owner Essex Phillips Petroleum Company

Lease Name Carr Well No. 1

Office Address Wartlesville, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed April 5 19 62

Application for plugging filed April 4 19 62

Application for plugging approved April 5 19 62


Plugging commenced April 4 19 62

Plugging completed April 5 19 62

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production ----- 19 ---

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Fred W. Kämpel

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 516 1/2 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		Surface	23 1/2	8-5/8		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud in hole from 516 1/2' to 250. 1 plug at 250 with 1/4 sack hulls and 20 sacks cement. Mud to 40'. 1 plug with 1/4 sack hulls, 10 sacks cement and welded cap on top of surface pipe. 2 sacks cement in rat hole. Completed at 7:00 P.M.

RECEIVED
STATE CORPORATION COMMISSION

DEC 17 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Season Drilling, Inc.

Address 1023 Season Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SANDWICK, ss.

Dale R. Green (employee of owner) or (owner/oper) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale R. Green

Dale R. Green
(Address) 1023 Season Bldg., Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 20th day of April, 19 62 Wichita, Kansas

Ethel L. Marshall
Notary Public.

My commission expires September 19, 1963

R

DRILLER'S LOG

OPERATOR: D. G. Hamilton
CONTRACTOR: Beacon Drilling, Inc.
WELL: #1 Carr
LOCATION: NE/4 SE/4, Sec. 14-34S-7W
Harper County, Kansas
COMMENCED: February 5, 1962
COMPLETED: April 5, 1962
SURFACE PIPE: 254' 8-5/8 with 135 sacks cement

255 - 690	Red beds
690 - 1150	Shale and shells
1150 - 1385	Shale and lime
1385 - 1420	Lime
1420 - 1495	Shale
1495 - 1925	Lime
1925 - 2035	Shale and lime
2035 - 2100	Shale
2100 - 2130	Shale and lime
2130 - 2285	Shale and shells
2285 - 2555	Shale and lime
2555 - 2610	Shale and shells
2610 - 2753	Shale
2753 - 2990	Shale and lime
2990 - 3035	Shale
3035 - 3115	Shale and lime
3115 - 3145	Lime
3145 - 3159	Shale and lime
3159 - 3189	Lime
3189 - 3839	Shale and lime
3339 - 3370	Lime
3370 - 3435	Shale and lime
3435 - 3500	Lime
3500 - 3557	Shale and lime
3557 - 3663	Sandy shale and lime
3663 - 3736	Shale and lime
3736 - 3770	Shale
3770 - 3780	Shale and lime
3780 - 3782	Shale
3782 - 3828	Stal. sand
3828 - 3915	Sand and shale
3915 - 3985	Shale and lime
3985 - 4041	Shale
4041 - 4282	Lime
4282 - 4665	Shale and lime
4665 - 4913	Lime
4913 - 4939	Shale and lime
4939 - 4985	Lime
4985 - 5155	Shale and lime
5155 - 5164	Simpson sand
5164	T.D. D & A

RECEIVED
STATE CORPORATION COMMISSION

MAR 23 1962

CONSERVATION DIVISION
Wichita, Kansas

I, Dale R. Green, President, Beacon Drilling, Inc., do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Carr, located in the NE/4 SE/4 of Section 14-34S-7W, Harper County, Kansas, as reflected by the files of Beacon Drilling, Inc.

BEACON DRILLING, INC.

By: *Dale R. Green*
Dale R. Green, President

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

Be it remembered that on this 20th day of April, 1962, before me, Esther L. Marshall, a Notary Public, personally appeared Dale R. Green, the President of Beacon Drilling, Inc. a corporation which is personally known to me, and known to me to be the President of said corporation and the same person who executed the foregoing instrument, and he duly acknowledged to me the execution of same for and on behalf of and as the act and deed of said corporation.

IN WITNESS WHEREOF, I have hereunto set my hand and affixed my official seal in the day and year written above.

Esther L. Marshall
Notary Public

My Commission expires Sept. 19, 1963.

RECEIVED
STATE CORPORATION COMMISSION
APR 22 1962
CONSERVATION DIVISION
With _____