

15-007-20152-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec 27 Twp 31S Rge (E) 11 (W)
Location as "NE/CNW&SW" or footage from lines NW NE SW
Lease Owner Beacon Resources Corporation
Lease Name Stephenson Well No. 1
Office Address 1000 Century Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 11, 19 70
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced June 11, 19 70
Plugging completed June 11, 19 70
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein of Attica, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4560 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	251'	8-5/8"	251'	None
	Casing					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy Mud from Total Depth to 240 Feet;
1/2 sax Hulls, Plug & 25 sax Cement; Mud
to 40 Feet, 1/2 sax Hulls, Plug Bridged
w/Kelly & 10 sax Cement to Base of Cellar;
2 sax Cement in Rat Hole. Job Completed
@ 11:00 P.M. on 6/11/70.

RECEIVED
STATE CORPORATION COMMISSION
6-17-70
JUN 17 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Sage Drilling Co., Inc.
Address 500 Bitting Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
T. M. McCaul, Jr. of Sage Drilling (employee of owner or contractor) of the above described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. M. McCaul, Jr.
500 Bitting Building, Wichita, Kansas
(Address)



SUBSCRIBED AND SWORN to before me this 15th day of June, 1970
Louise K. Whitted
Louise K. Whitted - Notary Public.
November 26, 1970

DRILLERS LOG

STEPHENSON NO. 1

CASING RECORD:	OPERATOR:	Beacon Resources Corporation	DESCRIPTION:
8-5/8" @ 251'	CONTRACTOR:	Sage Drilling Co., Inc.	NW NE SW
w/200 sax cement	COMMENCED:	June 1, 1970	Sec. 27-31S-11W
TOTAL DEPTH:	COMPLETED:	June 11, 1970	Barber Co., Kansas
4560'			ELEVATION: 1715 KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	65	
Red Rock & Shale	65	252	
Shale & Red Bed	252	700	
Shale & Shells	700	1550	
Shale & Lime	1550	1855	
Lime & Shale	1855	2496	
Shale & Lime	2496	3055	
Lime & Shale	3055	3511	
Lime, Shale & Sand	3511	3750	
Shale & Lime	3750	3890	
Lime	3890	3955	
Lime & Shale	3955	4033	
Lime	4033	4158	
Shale & Lime	4158	4227	
Lime & Chert	4227	4300	
Lime	4300	4363	
Lime & Shale	4363	4423	
Lime	4423	4505	
Mississippi	4505	4520	
Mississippi Chatt	4520	4560	D&A

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1970
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

T. M. McCaul, Jr.

By _____
T. M. McCaul, Jr.



Subscribed and sworn to before me this 15th day of June, 1970.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.