


15-007-10049-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County. Sec. 30 Twp. 31 Rge. 11 (E) W (W)
Location as "NE/CNW/SW" or footage from lines. N/2 SW SE
Lease Owner Aylward Drilling Co.
Lease Name Swartz #3 "A" Well No.
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed JAN. 1953
Application for plugging filed AUG. 1959
Application for plugging approved JAN. 1960
Plugging commenced 9-25-59 19
Plugging completed 9-29-59 19
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Lackamp
Producing formation MISS. Depth to top 4266 Bottom Total Depth of Well 4297 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	122'	None
				5 1/2"	4268'	2807'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 3342' and found it open.
Filled w/sand to 3300' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" casing.
Cleared hole and check mud to 700', mudded the hole to 120', bailed fluid to 120', set 10' rock bridge and dumped 20 sacks of cement.
Mudded the hole to 40', set 10' rockbridge and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECEIVED
STATE CORPORATION COMMISSION
JAN 21 1960
1-21-60
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
I, Noel J. Knight (employee of owner) or (agent) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of September, 1959

My commission expires 9-27-62
Thomas V. Dyer Notary Public.



15-007-10049-0000
 SWARTZ #3-A

Casing Record:

8-5/8" 122'
 5-1/2" 4268'

Company: Aylward Drilling Company
 Contractor: Aylward Drilling Company

Commenced: January 1, 1953
 Completed: January 24, 1953

Location:
 N $\frac{1}{2}$ SW SE Sec. 30-31-11W
 Barber County, Kansas

Elevation: 1521 R.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay	0	20	
Sand	20	40	
Shale	40	70	
Shale & Shells	70	160	Set 122' 8-5/8" with 75 sacks cement.
Shale & Shells & Redbed	160	730	
Shale & Shells	730	1520	
Lime & Shale	1520	1630	
Lime	1630	1750	
Lime & Shale	1750	2010	
Lime	2010	2310	
Shale & Lime	2310	2800	
Lime	2800	2980	
Lime & Shale	2980	3295	
Shale	3295	3330	
Broken Shale & Lime	3330	3350	
Sand & Shale	3350	3360	
Shale & Lime	3360	3455	
Lime & Sand	3455	3560	
Lime & Shale	3560	3685	
Sand & Lime	3685	3705	
Lime	3705	4275	T.D. Set 4268' 5-1/2" casing with 250 sacks pozmix.

CABLE TOOL

Chert 4275 4297 T.D.

TOPS

Elgin 3342
 Heebner 3468
 Base Oread 3494
 Douglas Sand 3542
 Lansing-Kansas City 3693
 Mississippi 4266

STATE CORRELATION COMMISSION
 JAN 21 1960
 1-21-60
 CONSERVATION DIVISION
 Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

Al Skalsky
 Al Skalsky

Subscribed and sworn to before me this 20th day of March 1953.

Flora Cooper
 Notary Public

My commission expires: July 16, 1956.