


15-007-10047-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 30 Twp. 31 Rge. 11 (E) W (W)
Location as "NE/CNW/SW" or footage from lines CS/2 N/2 NE
Lease Owner Aylward Drilling Co.
Lease Name Nuckolls "B" #3 Well No.
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed January 19 52
Application for plugging filed May 22 19 59
Application for plugging approved May 26 19 59
Plugging commenced 5-27-59 19
Plugging completed 6-2-59 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Lackamp
Producing formation Depth to top Bottom Total Depth of Well 4338 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	125'	none
				7"	4313'	3362'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 4338' and found it open.
Filled w/sand to 4310' and dumped 5 sacks of cement. Pulled 7" casing, cleared hole and bailed to good mud at 160', set rock bridge to 150' and dumped 25 sacks of cement. Mudded the hole to 40', set rock bridge to 30' and ran 15 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1962
6-27-62
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
I, Noel J. Knight (employee of owner) or (owner/property) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of June, 19 59

9-27-62
Thomas V. Dwyer
Notary Public.

My commission expires



NUCKOLLS "B" NO. 3

Casing Records:

10 3/4" - 162'
7" - 4313'

Company: W. J. Coppinger-Metropolitan & Aylward
Contractor: W. J. Coppinger

Commenced: December 1, 1951
Completed: December 31, 1951

Location:
C S $\frac{1}{2}$ N $\frac{1}{2}$ NE $\frac{1}{4}$
Sec. 30-31-11W
Barber County
Kansas
Elevation: 1553 RB

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand	0	80	Set 10 3/4" surface pipe @ 162' w/75 sacks cement
Shells & Sand	80	105	
Shale & Shells	105	135	Geological Tops:
Shale	135	162	
Red bed, Sand & Gravel	162	350	Elgin Sandstone 3405
Red Bed, Shells & Shale	350	440	Oread 3550
Red Bed & Shale	440	754	Douglas 3636
Shale & Shells	754	1530	Lansing-K.C. 3710
Lime & Shale	1530	1995	Basal Penn. Congl. 4293
Shale	1995	2045	
Lime	2045	2050	
Lime & Shale	2050	2110	
Lime	2110	2150	
Lime & Shale	2150	2315	
Shale & Lime, broken	2315	2400	
Lime & Shale	2400	2500	
Shale & Shells	2500	2600	
Shale	2600	2815	
Shale & Lime	2815	3095	
Shale	3095	3100	
Lime & Shale	3100	3210	
Shale & Shells	3210	3335	
Lime & Shale	3335	3357	
Shale, Lime broken	3357	3391	
Lime	3391	3405	
Sand	3405	3415	
Shale, sandy	3415	3523	
Lime, Shale & Sand	3523	3620	
Shale	3620	3630	
Douglas Sand & Shale	3630	3710	
Lansing Lime	3710	3738	
Lime	3738	3913	
Lime & Shale	3913	3972	
Lime	3972	4068	
Lime & Shale	4068	4098	
Cherty Lime & Shale	4098	4140	
Lime & Shale	4140	4159	
Lime	4159	4167	
Lime & Shale	4167	4308	
Chert, Lime & Shale	4308	4326	T.D. Set 7" casing @ 4313' w/100 sax cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1962
6-27-62
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse

Subscribed and sworn to before me this 11th day of August, 1959

Duane Jessup
DUANE JESSUP Notary Public

My commission expires December 11, 1961