


15-007-10045-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 30 Twp. 31 Rge. 11 (W)
Location as "NE/CNW&SW&E" or footage from lines N 1/2 SE SE
Lease Owner Aylward Drilling Company
Lease Name Swartz A #4 Well No. _____
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed April 1, 1954
Application for plugging filed May 19 1957
Application for plugging approved May 20 1957
Plugging commenced 6-21-57 19
Plugging completed 6-26-57 19
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production May 1957
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Merle Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4320 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	200'	none
				5 1/2	4300'	2906'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled w/sand to 3510' and ran 5 sacks cement.
Baled hole to 210' and filled w/mud. Set a 10'
rock bridge and ran 20 sacks cement to 130'.
Mudded hole to 45' and set a 10' rock bridge.
Ran 10 sacks cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Paul W. Hesse (employee of owner) or (~~owner or operator~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse

813 1st Natl. Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of June, 19 57

My commission expires 9-27-58

Thomas C. Higgins
RECEIVED
CORPORATION COMMISSION
Notary Public.

PLUGGING
FILE SEC. 30 T. 31 R. 11W
BOOK PAGE 13 LINE 33

JUL 2 - 1957
72-57
CONSERVATION DIVISION
Wichita, Kansas

15-007-10045-0000

SWARTZ #4 "A"

Casing Record:
 8-5/8" 136'
 5-1/2" 4288'

Company: Aylward Drilling Company et al
 Contractor: Aylward Drilling Company
 Commenced: March 8, 1954
 Completed: April 1, 1954


Location:
 N½ SE SE
 30-31-11W
 Barber County, Kansas
 Elevation: 1537 R.B.
 1534 D.F.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Sand & Redbed	0	90	
Redbed	90	136	Set 136' of 8-5/8" Casing, cement with 85 sacks
Redbed & Shale	136	920	
Shale	920	1255	
Shale & Shells	1255	1400	
Anhydrite	1400	1460	
Sandy Lime & Shale	1460	1620	
Lime & Shale	1620	2025	
Lime	2025	2215	
Lime & Shale	2215	2325	
Sandy Lime	2325	2345	
Lime & Shale	2345	2676	
Shale	2676	2790	
Lime	2790	2965	
Lime	2965	3110	
Lime & Shale	3110	3380	
Shale	3380	3383	
Sand	3383	3391	
Shale & Lime	3391	3529	
Sand	3529	3575	
Sand & Shale	3575	3708	
Shale & Lime	3708	3810	
Lime	3810	3914	
Shale	3914	3939	
Lime & Shale	3939	4026	
Lime	4026	4070	
Shale & Lime	4070	4140	
Lime	4140	4175	
Lime & Shale	4175	4265	
Lime	4265	4276	
Shale	4276	4286	
Miss. Lime	4286	4291	T.D. Set 4288' 5-1/2" Casing, cement with 250 sacks of Pozmix.

TOPS:

Elgin Sand	*3378	(-1842)
Heebner	*3478	(-1942)
Douglas Sand	3529	(-1992)
Lansing - K.C.	3715	(-2178)
Mississippi	4286	(-2749)
R.T.D.	4291	(-2754)

*Corrected 4' up hole S.L.M.



CABLE TOOL WORK

Drilled deeper to 4307 and plugged back to 4295. Sandoil treatment.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesse
 Paul W. Hesse
 NOTARY PUBLIC
 CONSERVATION COMMISSION

Subscribed and sworn to before me this 10th day of April, 1954.

JUL 2 - 1957
 7-2-57
 CONSERVATION DIVISION
Duan
 Notary Public

My Commission Expires: 12-11-57