


15-007-10044-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 30 Twp. 31 Rge. (E) 11 (W)

Location as "NE/CNW&SW&" or footage from lines C NE NE
Lease Owner Aylward Drilling Company
Lease Name Nuckolls "B" Well No. 1
Office Address 813 1st Nat'l Bank Bldg. - Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed August 3 1940
Application for plugging filed May 22 1959
Application for plugging approved May 26 1959
Plugging commenced June 1 1959
Plugging completed June 6 1959
Reason for abandonment of well or producing formation depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production May 1959
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Lackamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4337 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	131'	None
				5 1/2"	4299'	1701'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked the hole to 4330' and found it open.
Filled w/sand to 4290' and dumped 5 sacks of cement with baller. Pulled 5 1/2" casing, cleared hole and checked fluid to 15' and mud to 170'.
Mudded the hole to 130', bailed fluid to 130', set rock bridge to 123' and dumped 20 sacks of cement. Mudded the hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECEIVED
STATE CORPORATION COMMISSION
7-23-59
JUL 23 1959

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co. Conservation Division
Address Chase, Kansas Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Paul W. Hesse (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse
813 1st Nat'l Bank Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of June, 1959

My commission expires December 11, 1961

Diane Jessup Notary Public.

PLUGGING
FILE SEC 30 T. 31 R. 11W
BOOK PAGE 40 LINE 21

RECEIVED
STATE CORPORATION COMMISSION

JUL 23 1959
7-23-59
CONSERVATION DIVISION
Wichita, Kansas

NUCKOLLS "B" NO. 1

Casing Records: Company: Olson Oil Company Location: C N E NE 30-31-11W
Contractor: Olson Oil Company Barber County, Kansas
8 5/8" - 131'
5 1/2" - 4299'
Commenced: July 2, 1940
Completed: July 29, 1940

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Cellar	0	10	Set 8 5/8" surf. pipe @ 131' w/50 sacks cement.
Sandy Clay	10	55	
Red Rock	55	220	
Red Shale & Shells	220	370	Geological Tops:
Shale & Shells	370	1135	
Salt	1135	1426	Lansing 3710
Shale	1426	1515	Chat 4293
Shale & Shells	1515	1536	
Shale & Shells, Hard	1536	1581	
Shale & Gyp	1581	1629	
Shale & Lime, Hard	1629	1698	
Lime	1698	1759	
Anhydrite & lime	1759	1804	
Shale & Lime	1804	1840	
Broken Lime & Shale	1840	1887	S.L. Correction 3754
Lime	1887	1970	Lime 3757
Lime, Hard	1970	1995	Lime & Shells 2812
Broken Lime	1995	2059	Lime 3887
Lime	2059	2166	Hard Lime & Chert 3924
Blue Shale	2166	2200	Lime 3924
Lime	2200	2239	Lime 3931
Broken Lime	2239	2268	Lime & Chert 4009
Blue shale, Lime, Shells	2268	2290	Lime Hard 4065
Lime & Shale	2290	2312	Lime & Shale 4107
Shale	2312	2333	Lime 4124
Shale & Lime	2333	2362	Lime 4183
Shale & Lime, Soft	2362	2395	Broken Lime 4205
Shale & Lime	2395	2445	Shale 4221
Broken Lime	2445	2476	Shale & Lime 4221
Lime & Shale	2476	2624	Broken Lime 4262
Shale	2624	2722	Lime & Shale 4289
Shale & Shells	2722	2843	Lime & Shale 4289
Lime	2843	2938	Var. Shale 4293
Lime & Shale	2938	3040	Chert 4302
Shale	3040	3066	Corrected 4307
Sandy Shale, soft	3066	3082	Chat, soft - T.D. 4300
Lime	3082	3144	
Shale	3144	3188	
Lime	3188	3241	Set 5 1/2" casing @ 4299 w/300 sacks cement.
Shale	3241	3300	
Lime & Shale	3300	3370	
Sandy Lime & Shale	3370	3461	
Lime & Shale	3461	3507	
Lime & Shale, soft	3507	3602	
Sandy Shale, soft	3602	3707	
Lime	3707	3754	

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Paul W. Hesser

Subscribed and sworn to before me this 22nd day of July, 1959

Duane Jessup
DUANE JESSUP Notary Public

My commission expires December 11, 1961

PLUGGING
FILE SEC 30T.31 R.11W
BOOK PAGE 40 LINE 27