

15-007-30273-00-00

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Barber County. Sec. 7 Twp. 30S Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SE

Lease Owner Ferguson Oil Company

Lease Name Rose Well No. 1

Office Address 1505 Wichita Plaza Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12-1-66 19

Application for plugging filed 12-1-66 19

Application for plugging approved 12-1-66 19

Plugging commenced 12-1-66 19

Plugging completed 12-1-66 19

Reason for abandonment of well or producing formation

commercial quantities of oil not found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving - Pratt, Kansas 4044'

Producing formation Depth to top Bottom Total Depth of Well 4640 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	299'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug @ 275' w/ 25 sacks cement.  
Plug @ 40' w/ 10 sacks cement.  
2 sacks in rathole

RECEIVED  
STATE CORPORATION COMMISSION

DEC 5 1966

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Walters Drilling Co.

Address 400 Insurance Building - Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Robert F. Walters (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Robert F. Walters

400 Insurance Building - Wichita, Kansas 67202 (Address)

SUBSCRIBED AND SWORN to before me this 5th day of December, 1966

My commission expires October 4, 1967

Juanita M. Green Notary Public.



DRILLER'S LOG

COMPANY: FERGUSON OIL COMPANY  
1505 WICHITA PLAZA BUILDING  
WICHITA, KANSAS 67202

WELL NAME: ROSE #1  
SW SE SEC. 7-30S-12W  
BARBER COUNTY, KANSAS

CONTRACTOR: WALTERS DRILLING CO.  
400 INSURANCE BUILDING  
WICHITA, KANSAS 67202

ROTARY DRILLING COMMENCED: NOVEMBER 17, 1966  
ROTARY DRILLING COMPLETED: DECEMBER 1, 1966

ELEVATION: 1871 KB

CASING RECORD: 8 5/8" @ 299' w/ 200 sx. cement.

LOG

0 - 30	Surface Clay and Sand
30 - 120	Sand
120 - 175	Shale
175 - 300	Red Bed
300 - 800	Red Bed and Shale
800 - 1132	Shale and Red Bed
1132 - 1500	Shale and Shells
1500 - 1750	Shale, Lime and Shells
1750 - 1995	Shale and Lime
1995 - 2130	Lime and Shale
2130 - 2250	Lime
2250 - 3095	Lime and Shale
3095 - 3350	Shale and Lime
3350 - 3495	Lime and Shale
3495 - 3610	Shale and Lime
3610 - 3837	Lime and Shale
3837 - 3935	Shale and Lime
3935 - 4425	Lime
4425 - 4495	Shale and Lime
4495 - 4499	Shale and Sand
4499 - 4527	Sand (Simpson)
4527 - 4560	Lime and Shale
4560 - 4585	Lime and Chert
4585 - 4600	Lime
4600 - 4644	Lime and Sand
4644	<u>Rotary Total Depth - D &amp; A</u>

**RECEIVED**  
STATE CORPORATION COMMISSION

DEC 5 1966

CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, Robert F. Walters, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

BY

  
ROBERT F. WALTERS, Partner

Subscribed and sworn to before  
me this 5th day of December,

1966

  
  
Juanita M. Green, Notary Public

My Commission Expires: October 4, 1967