

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-21,829-00-00

LEASE NAME Rose B

WELL NUMBER 1-7

SPOT LOCATION E/2 NE NE

SEC. 7 TWP. 30 RGE. 12(E) or (W)

COUNTY Barber

Date Well Completed 6-5-84

Plugging Commenced 5:15 PM

Plugging Completed 6-5-84

Plugging Completed 6:30 PM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR F. G. Holl

ADDRESS 6427 East Kellogg
Wichita, Kansas 67207

PHONE # (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dist. #1

Is ACO-1 filed? _____ If not, is well log attached? yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 4772'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10 3/4"	251.34'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Ran 50 sacks at 4770'; Heavy mud to 740', 40 sacks at 740';

Heavy mud to 310', 50 sacks at 310'; Plug and circulate

10 sacks at 40'; circulated 15 sacks in rathole & 10 sacks

in mousehole. Used 60-40 Pozmix, 2% Gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company License No. 5142

Address PO Box 129, Sterling, Ks 67579

STATE OF Kansas COUNTY OF Rice, ss.

Harry J. Mead

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION

(Signature) Harry J. Mead
STERLING DRILLING COMPANY

Harry J. Mead, Vice Pres.

(Address) PO Box 129, Sterling, Ks 67579

JUN 13 1984

SUBSCRIBED AND SWORN TO before me this 6 day of June, 19 84

CONSERVATION DIVISION
Wichita, Kansas

My Commission expires:



F. A. Wuellner
Notary Public

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - Rose B 1-7

Located: E/2 NE NE, Sec. 7-30S-12W, Barber
County, Kansas

OWNER: F.G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 25, 1984

COMPLETED: June 5, 1984

TOTAL DEPTH: 4772'

LOG

0 - 55'	Sand & Clay
55 - 266'	Sand & Red Bed
266 - 825'	Shale
825 - 1007'	Red Bed & Shale
1007 - 1500'	Shale
1500 - 4772'	Lime & Shale

CASING RECORD

Ran 6 joints 10 3/4" new casing
251.34' pipe set at 264' KB.
Cemented with 240 sacks Common,
2% Gel, 3% cc. Plug down at
8:15 PM by Howco.

Plugged

DEVIATION SURVEYS

1 1/4°	at 2088'
1'	at 3764'
1°	at 4318'
1 1/4°	at 4520'
1 1/4°	at 4772'

RECEIVED
STATE CORPORATION COMMISSION

JUN 13 1984

CONSERVATION DIVISION
Wichita, Kansas