

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-21590-00-00

LEASE NAME Rose 1-8

WELL NUMBER \_\_\_\_\_

SPOT LOCATION NE NE SW

SEC. 8 TWP. 30S RGE. 12W (E) or (W)

COUNTY Barber

Date Well Completed \_\_\_\_\_

Plugging Commenced 2-21-84

Plugging Completed 2-23-84

LEASE OPERATOR F.G. Holl

ADDRESS 427 E. Kellogg Wichita, Ks. 67207

PHONE (316) 684-8481 OPERATORS LICENSE NO. 5056

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4744'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				4-1/2"	4734'	3211'
				10-3/4"	276'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4200' and ran 4 sacks cement. Shot casing @ 3600', 3400', 3230' and pulled a total of 78 joints (4734') of 4-1/2" casing. Plugged surface with 2 hulls, 10 gel, 50 cement, 2 hulls, 10 gel, released plug and displaced with 120 cement, 60/40 pos, 2% gel, 3% cc. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED

STATE CORPORATION COMMISSION

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

MAR 07 1984

SUBSCRIBED AND SWORN TO before me this 5th day of March, 1984

CONSERVATION DIVISION  
Wichita, Kansas  
My Commission expires: \_\_\_\_\_



Irene Hoover  
Notary Public