

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-007-21,812-00-00

LEASE NAME Rose A

WELL NUMBER 1-8

 Ft. from S Section Line

W/2 NW NW Ft. from E Section Line

SEC. 8 TWP. 30S E. 12W (E) or (W)

COUNTY Barber

Date Well Completed

Plugging Commenced 3-9-89

Plugging Completed 3-14-89

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR F.G. Holl

ADDRESS P.O. Box 158 Belpre, Kansas 67519

PHONE# (316) 995-3171 OPERATORS LICENSE NO. 5056

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 13, 1989 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4800

Show depth and thickness of all water, oil and gas formations.

PBTD 4370
 Perfs: 4301-05

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	253	10 3/4	253	0
		253	4788	4 1/2		2247'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Dumped sand to 50' above top perfs, dumped 5 sx. cement, cut & pulled pipel.
3-14-89: Halliburton pumped 400# hulls, 10 gel, 50 sx. cement, 10 gel, 100# hulls,
plug, 125 sx. cement. Max. 300#, SIP 350#.

(If additional description is necessary, use BACK of this form)

Name of Plugging Contractor Pratt Well Service, Inc. License No. 5893

Address P.O. Box 847 Pratt, Kansas 67124

RECEIVED
 STATE CORPORATION COMMISSION
 4-7-89
 APR 7 1989

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: F. G. Holl

STATE OF Kansas COUNTY OF Pratt

CONSERVATION DIVISION
 Wichita Kansas

Judy Berry (Employee of prugging contractor) o
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts
 statements, and matters herein contained and the log of the above-described well as filed the
 the same are true and correct, so help me God.

(Signature) Judy Berry

(Address) P.O. Box 847 - Pratt, Ks.



SUBSCRIBED AND SWORN TO before me this 5th day of April, 19 89

Dorothy M. Ferguson
 Notary Public
 My Commission Expires February 6, 1993

STERLING DRILLING CO.

BOX 129

STERLING, KANSAS 67579

WELL LOG ----- ROSE "A" #1-8

Located: C W/2 NW NW, Section 8-30S-12W, Barber County,
Kansas

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: May 14, 1984

COMPLETED: May 24, 1984

TOTAL DEPTH: 4800

LOG

0 - 140 Sand and Clay
140 - 258 Red Bed
258 - 1009 Shale
1009 - 4800 Lime and Shale

CASING RECORD

Ran 6 joints 10 3/4" OD casing. 240.93'
pipe set at 253' K.B. Cemented with 240
sacks Common, 2% gel and 3% cc. Plug
down at 3:30 AM, 5-15-84, by Howco.

Ran 121 joints 4 1/2" OD casing. 4820.17'
pipe set at 4798' K.B. Cemented with 150
sacks Howco Lite, 150 sacks F. G. Holl mix
behind 500 gal. salt flush. 5 sacks in
mousehold and 10 sacks in rathole. Plug
down at 8:45 PM, 5-24-84, by Howco.

Deviation Surveys: 1 1/2° at 2023'
1 1/2° at 2799'
1 1/4° at 3779'
1° at 4678'
1° at 4880'