

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Barber County. Sec. 3 Twp. 30 Rge. 12W (~~E~~) (W)
Location as "NE/CNW&SW" or footage from lines C NE SW

Lease Owner W. C. Payne

Lease Name Gibson Well No. 1

Office Address 800 United Founders Tower Oklahoma City, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) D&A

Date well completed _____ 19____

Application for plugging filed _____ 19____

Application for plugging approved _____ 19____


Plugging commenced _____ September 11, 1967

Plugging completed _____ September 11, 1967

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4707 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|------|--------|------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

378' of 8 5/8" surface pipe, cement circulated with 300 sacks. Hole was filled with drilling mud to 300, 1st cementing plug, bridged with 1/2 sack of hulls on fluid at 300', and cemented with 20 sacks, with cement from 290' to 230'. Hole was filled with drilling mud to 35', 2nd cementing plug bridged with 1/2 sack of hulls on fluid at 35', and cemented with 8 sacks, with cement from 25' to the base of the cellar. Rat and mouse holes bridged and cemented with 4 sacks.

RECEIVED
STATE CORPORATION COMMISSION
MAY 8 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company

Address R. R. # 2 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

A. G. Radke (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Garvey Drilling Co., Route 2, Great Bend, Kan.
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of May, 1968

My commission expires November 5th, 1969

[Signature]
Notary Public.

WELL LOG

COMPANY **William C. Payne**

SEC. 3 T. 30S R. 12W

FARM **Gibson** NO. **1**


LOC. NE SW

TOTAL DEPTH **4707'**

COUNTY **Barber**

COMM. **8-29-67** COMP. **9-11-67**

CONTRACTOR **Garvey Drilling Company**



CASING **8 5/8" @ 378' w/200 EX**

ELEVATION

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

150' Sand
 625' Red Bed and Shale
 992' Red Bed
 1165' Shale and Red Bed
 2123' Shale and Lime
 2920' Lime and Shale
 3010' Shale and Lime
 3710' Lime and Shale
 3765' Shale and Lime
 3840' Shale
 4245' Lime
 4325' Lime and Shale
 4343' Lime
 4480' Lime and Shale
 4522' Cherty Lime
 4570' Lime
 4607' Sand
 4707' Lime and Shale
 4707' RTD

RECEIVED
 STATE CORPORATION COMMISSION
MAY 8 1968
 CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas
 County of Barber } ss

I, Sam H. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Gibson No. 1 well.

Subscribed and sworn to before me this 13th day of September, 1967

Sam H. Stephens

My Commission Expires: November 5th, 1969

Richard A. Doy
 NOTARY PUBLIC