

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barber County. Sec. 5 Twp. 30 Rge. (E) 12 (W)

Location as "NE/CNW&SW" or footage from lines SW ~~NE~~ NW

Lease Owner Roger F. Williams

Lease Name John Ball Well No. 1

Office Address 9 1/2 E. Main, Chanute, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 4 19 64

Application for plugging filed October 3 19 64

Application for plugging approved October 3 19 64


Plugging commenced October 4 19 64

Plugging completed October 4 19 64

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Herman Justus & Archie Elving

Producing formation None Depth to top Bottom Total Depth of Well 4740 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Sand</u>	<u>Water</u>	<u>10</u>	<u>186</u>	<u>8 5/8</u>	<u>305</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled w/rotary mud from 280 to 4740 feet
Set bridge at 280' - ran 25 sax
Filled w/rotary mud to 40'
Set bridge at 40' - ran 10 sax and filled to surface
Ran 2 sax in rat-hole

RECEIVED
STATE CORPORATION COMMISSION

OCT 9 - 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E Drilling Company

Address Wichita, Kansas

STATE OF Kansas COUNTY OF Neosho, ss.

James E. Guinotte (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James E. Guinotte

9 1/2 E. Main, Chanute, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of October, 19 64

My commission expires March 31, 1965

Verte Paul Moore
Notary Public.

DRILLER'S WELL LOG

OPERATOR: Roger F. Williams Oil Co.
3420 SW 9th Street
Des Moines, Iowa

WELL NAME: #1 John Ball
LOCATION: Approx. C SW NW
Sec. 5-30S-12W
Barber Co., Kansas

CONTRACTOR: **K & E DRILLING, INC.**
719 UNION CENTER BLDG.
WICHITA, KANSAS

COMMENCED: 9-22-64

CASING RECORD: 8-5/8" @314' w/275 sx.

COMPLETED: 10-4-64

ELEVATION:

ROTARY TOTAL DEPTH: 4740'

PRODUCTION: D & A

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Sand	185
Shale & Red Bed	765
Shale	1575
Lime & Shale	2400
Lime	2560
Shale & Lime	2985
Lime	4644
Sand & Shale	4683
Sand	4710
Lime	4740

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1964

CONSERVATION DIVISION
Wichita, Kansas

CERTIFICATION

State of KANSAS }
County of SEDGWICK } ss:

I, Wayne L. Brinegar, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Subscribed and sworn to before me this 7th day of October, 1964

My Commission expires: August 30, 1965

Julene M. Bannon
Julene M. Bannon Notary Public.

