

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-21,890

LEASE NAME Martin

WELL NUMBER #1

SPOT LOCATION N/2-NE NE

SEC. 1 TWP. 30 RGE. 12 (E) or (W)

COUNTY Barber

Date Well Completed \_\_\_\_\_

Plugging Commenced 1-10-86

Plugging Completed 1-23-86

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Carl Dudrey

ADDRESS Box 65, St. John, Kansas 67576

PHONE # 316-549-3235 Office  
316-549-5505 OPERATORS LICENSE NO. 8045

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? One (1)

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3890'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	341'	None
				5-1/2"	3889'	1,757.76'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 3420' and 5 sacks cement. Shot casing at 1900' and 1800'. Pulled 42 joints of 5-1/2" casing. Allied squeezed well with 2 sacks hulls, 15 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 130 sacks 60/40 pozmix cement with 6% added gel. Maximum pressure was 400 psi and shutin 200 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111  
Address Box 698, Great Bend, Ks. 67530

RECEIVED  
STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss.

JAN 27 1986

James W. Rockhold (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold  
(Address) James W. Rockhold  
Box 698, Ct. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 24th day of January, 1986

STATE NOTARY PUBLIC  
KANSAS  
IONA M. LEATHERMAN  
Barton County, Kansas  
My Appt. Exp. 9-26-87

My Commission expires:

Iona M. Leatherman  
Notary Public

DRILLERS LOG

#1 MARTIN  
N/2 NE/4 NE/4 Section 1-30-12W  
Barber County, Kansas

OPERATOR: CARL DUDREY  
Box 65  
St. John, Kansas 67576

CONTRACTOR: DUNNE-GARDNER PETROLEUM, INC.  
Suite 250, 200 West Douglas  
Wichita, Kansas 67202


COMMENCED: August 9, 1984

COMPLETED: August 16, 1984

<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	920	Sand and clay
920	1325	Sand and shale
1325	1889	Sand and clay
1889	1997	Sand and shale
1997	2183	Shale and lime
2183	2468	Shale and clay
2468	3625	Shale and lime
3625	3747	Sand and shale
3747	3890	Shale and lime
3890		Rotary total depth

STATE OF KANSAS    )  
                              ) ss  
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

  
Donald E. Hunt

Subscribed and sworn to before me this 17th day of August, 1984.

My appointment expires:  
January 20, 1985

  
Notary Public