

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County, Sec. 28 Twp. 31S Rge. 11 E/W
Location as "NE/CNW/SW" or footage from lines

NW NW NE

Lease Owner Graves Drilling Co., Inc.

Lease Name Stephenson Well No. 1

Office Address 910 Union Center, Wichita, Kansas 67202

Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed May 16, 1979

Application for plugging filed May 16, 1979

Application for plugging approved May 16, 1979

Plugging commenced May 16, 1979

Plugging completed May 16, 1979

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4516'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	219'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 210'. Pumped 40 sacks of cement through drill pipe with pump truck. Pushed plug and 1/2 sack hulls to 40 feet and pumped 12 sacks cement through drill pipe with pump truck to base of well cellar. Plugged rat hole with 3 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc., 910 Union Center, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
John C. Graves (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
910 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of May, 1979

Betty Brandt
Betty Brandt Notary Public.

My commission expires May 9, 1983

RECEIVED
STATE CORPORATION COMMISSION

MAY 23 1979
5-23-79
CONSERVATION DIVISION
Wichita, Kansas

R O T A R Y D R I L L E R S ' L O G

OPERATOR: Graves Drilling Co., Inc. DRILLING COMMENCED: May 8, 1979
 910 Union Center
 Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: May 16, 1979
 910 Union Center
 Wichita, Kansas 67202


CASING RECORD: 5 Jts. 219' of used 8-5/8" cemented with 225 sacks. LOCATION: Stephenson No. 1
 NW NW NE
 Section 28-31S-11W
 Barber County, Kansas

0 - 60	Sand
60 - 219	Red bed
219 - 952	Shale & Lime
952 - 1605	Sahle, Red Bed & Lime
1605 - 4348	Shale & lime
4348 - 4439	Lime & Shale
4439 - 4516	Lime
4516	Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By *J. L. Graves*
President



SS.

Subscribed and sworn to before me, a Notary Public, this 22nd day of May, 1979.

Betty Brandt
Betty Brandt Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 23 1979
 S-23-79
 CONSERVATION DIVISION
 Wichita, Kansas