

15-007-00740-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barber County, Sec. 28 Twp. 31S Rge. 11 (X) (W)

Location as "NE/CNW/SW" or footage from lines. SE NW NE
Lease Owner Parker Petroleum, Inc.
Lease Name Stephenson Well No. 1
Office Address P. O. Drawer 791 - Ponca City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8-14 19 56
Application for plugging filed 8-14 19 56
Application for plugging approved 8-14 19 56
Plugging commenced 8-14 19 56
Plugging completed 8-14 19 56
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4500 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Elgin Sand		3506		10 3/4	213	
Douglas		3692				
Kansas City		3906				
Mississippi		4437				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with heavy rotary mud to 200' - 1/4 sack hulls. Plug set with 25 sacks cement.
Top plug set at 30' cemented with 10 sacks cement. Hole plugged.

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1956
8-18-56
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor L. C. Smitherman Drilling Company
Address Box 627 - Augusta, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
Joe W. Cain (employee of owner) or (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe W. Cain
Box 627 - Augusta, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of August 19 56
Notary Public.

My commission expires October 23, 1958.

PLUGGING
FILE SEC. 28 T. 31 R. 11W
BOOK PAGE 90 LINE 35

STEPHENSON #1

Company - Parker Petroleum, Inc. Location: SE NW NB, Sec: 28-31S-11W,
 Contractor - E. C. Smitherman Drig. Co. Barber County, Kansas
 Elevation:
 Commenced - 7-23-56 Casing: 10 3/4" - 213' Cemented W/250 Sks
 Completed - 8-15-56
 Total Depth - 4500'
 Initial Prod. - D & A

Figures Indicate Bottoms of Formations:

Depth	Formation
0 - 40	Soil & Sand
40 - 115	Clay & Shale
115 - 213	Shale
213 - 345	Red Bed
345 - 625	Sand, Shale & Red Bed
625 - 745	Shale & Shells
745 - 1230	Red Rock & Shale
1230 - 1580	Shale & Shells, Red Rock
1580 - 1888	Lime & Shale
1888 - 1940	Lime
1940 - 2009	Lime & Shale
2009 - 2110	Lime
2110 - 2460	Lime & Shale
2460 - 2510	Shale & Lime
2510 - 2535	Lime & Shale
2535 - 2987	Shale & Lime
2987 - 3187	Lime & Shale
3187 - 3200	Shale & Lime
3200 - 3272	Lime
3272 - 3320	Lime W/Shale Strks.
3320 - 3485	Shale & Lime
3485 - 3525	Lime & Shale
3525 - 3602	Sandy Shale
3602 - 3632	Lime
3632 - 3649	Sandy Shale & Lime
3649 - 3705	Sandy Lime & Shale
3705 - 3770	Shale & Sand Strks.
3770 - 3780	Sandy Shale
3780 - 3862	Shale
3862 - 4085	Lime
4085 - 4127	Lime & Shale
4127 - 4246	Lime
4246 - 4258	Shale
4258 - 4352	Lime
4352 - 4439	Lime & Shale
4439 - 4467	Sand & Chert
4467 - 4496	Chert & Lime
4496 - 4500	Lime & Chert
4500 - R. T. D.	

We hereby certify the above and foregoing to be a true and correct copy of the Log on the Stephenson #1, located in the SE NW NE, of Section 28-31S-11W, Barber County, Kansas:

L. C. SMITHERMAN DRILLING COMPANY

[Handwritten Signature]

Subscribed and sworn to before me this 16th day of August, 1956.

[Handwritten Signature]
Notary Public

My commission expires October 23, 1958.

8-19-56

PLUGGING
 FILE SEC 28 T 31 R 11W
 BOOK PAGE 90 LINE 35