

15-007-10032-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County. Sec. 29 Twp. 31 Rge. 11 (E) W (W)
Location as "NE/CNWxSW" or footage from lines C NW SW
Lease Owner Aylward Drilling Company
Lease Name Whelan Well No. 2
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 3-16 19 52
Application for plugging filed 6-20 19 63
Application for plugging approved 6-21 19 63
Plugging commenced 6-28-63 19
Plugging completed 7-3-63 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production June 26, 1963
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation Miss. Depth to top 4351 Bottom 4358 Total Depth of Well 4358 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Miss.	Oil	4351	4358	8-5/8"	125'	None
				5-1/2"	4325'	2937'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4358', sanded to 4315' and dumped 5 sacks of cement @ 4315' with dump bailer. Pulled 5 1/2" casing, bailed fluid to 185', set rock bridge to 175' and ran 25 sacks of cement @ 175'. Mudded to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1963
9-17-63
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of July, 1963

My commission expires May 20, 1964

Milton J. Volin
Notary Public.

OLSON OIL CO.
F.H. Whelan No. 2.


15-007-10032-0000

SEC. 29 T. 31 R. 11W.
CNW SW

CORRECTED LOG

Total Depth. 4358
Comm. 4-2-40 Comp. 4-30-40
Shot or Treated.
Contractor.
Issued. 7-13-40

County Barber



CASING.

8" 128'
5" 4315'

Elevation.

Production. Pot. 943 B.

Figures Indicate Bottom of Formations.

sand	10	lime	3960
sand and red shale	115	shale and lime	3970
shale red	350	lime and shale	4007
shale red and shale	589	lime	4010
shale and shells	1185	lime and shale	4038
salt and shale	1560	lime	4082
lime	1723	lime and shale	4117
lime gyp and sand	1847	lime	4135
lime	2025	broken lime & shale	4151
broken lime and shale	2061	lime	4214
broken lime	2075	lime and shale	4326
lime	2158	shale variegated	4327
lime and shale	2206	chert firm	4328
shale	2225	lime, chert, chat firm	4330
lime and shale	2241	chat	4358
shells and shale	2308	Total Depth.	
shale and lime	2646		
lime	2665		
lime and shale	2757		
shale and shells	2841	Top Chat 4323	
lime	3079		
lime broken	3102		
lime	3135		
shale	3146		
lime	3202		
shale	3265		
lime and shale	3384		
shale and shells	3428		
shale and lime	3548		
lime	3570		
shale and shells	3625		
sdv shale	3655		
lime and sdv shale	3721		
lime	3724		
lime and shale	3749		
lime	3750		
lime sand and shale	3772		

RECEIVED
STATE CORPORATION COMMISSION

SEP 17 1963
9-17-63
CONSERVATION DIVISION
Wichita, Kansas